

#03-2-2114

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20339-00-01
Spot: NE Sec/Twnshp/Rge: 17-16S-7W
3960 feet from S Section Line, 1320 feet from E Section Line
Lease Name: SUNRIDGE FARM LTD Well #: 1
County: ELLSWORTH Total Vertical Depth: 1905 feet

Operator License No.: 5047
Op Name: RUPE OIL COMPANY, INC.
Address: PO BOX 783010 111 WHITTIER #1000
WICHITA, KS 67278

PROD Size: 4.5 feet: 1905 150 SX CMT
SURF Size: 7 feet: 213 100 SX CMT

6191
\$

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/29/2004 10:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTY ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Sand perforations to 1700'. Put 4 sacks of cement on top and cutoff casing. Pull to 850' and pump 35 sacks. Pull to 550' and pump 35 sacks. Pull casing to 265' and circulate cement to surface.
Plugging Method: _____
**RECEIVED
KCC DISTRICT #2
JUL 1 - 2004
WICHITA, KS**

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 06/29/2004 5:45 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 1650'. Put 4 sacks of cement on top. Attempted to cutoff casing at 829' and 562'. Casing appeared to have been squeezed. Perforated at 550' and 265'. Ran tubing to 550' and pumped 50 sacks of cement. Pulled tubing to 265' and circulated cement to surface.

60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
1764	1774		
1758	1759		

**RECEIVED
KANSAS CORPORATION COMMISSION
JUL 27 2004
CONSERVATION DIVISION
WICHITA, KS**

Remarks: COPELAND CEMENT #23539

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED
DATE 7-28-04
INV. NO. 2005060207