

#02-2-1417

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-10022-00-00
Spot: NESENE Sec/Twnshp/Rge: 6-30S-8W
1650 feet from N Section Line, 560 feet from E Section Line
Lease Name: POMEROY Well #: 2-6
County: KINGMAN Total Vertical Depth: 4289 feet

Operator License No.: 32825
Op Name: PIONEER EXPLORATION, LTD.
Address: 15603 KUYKENDAHL, SUITE 200
HOUSTON, TX 77090

PROD Size: 5.5 feet: 4289 200 SX CMT
SURF Size: 8.625 feet: 318 250 SX CMT

\$139.39

Well Type: GAS UIC Docket No: Date/Time to Plug: 06/10/2004 11:00 AM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed PBTB 4210'
Plugging Perf 4137'-4163'
Method: Sand to 4080' & 4 sxs; 1300' & 35 sxs; 750' & 35 sxs; 370' - circ
Rec 3000'

RECEIVED
KCC DISTRICT #2
JUN 24 2004
WICHITA, KS

Plugging Proposal Received By: STEVE VANGIESON

Witness Type: PARTIAL

Date/Time Plugging Completed: 06/10/2004 11:00 AM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:

The perforations were covered with sand to 4080' and capped with 4 sacks of cement. Casing recovered from 3000'. Pulled casing to 1300' and spotted 35 sacks of cement. Pulled casing to 750' and spotted 35 sacks of cement. Pulled casing to 370' and circulated cement to surface.

Top	Bot	Thru	Comments
4137	4163		

60/40 posmix with 4% gel & 4% CaCl

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 27 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENT

Plugged through: CSG

District: 02

Signed

(TECHNICIAN)

INVOICED

DATE

7-28-04

INV. NO.

2005060206