

RECEIVED

JUN 28 2004

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING APPLICATION  
Please TYPE Form and File ONE Copy

KCC WICHITA

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15-051-05016-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 12/30/48

Well Operator: VESS OIL CORPORATION KCC License #: 5030 6/05

Address: 8100 E. 22nd Street North, Bldg. 300 City: Wichita (Operator's)

State: KS Zip Code: 67226 Contact Phone: (316) 682-1537 X103

Lease: Gish C Well #: #1 Sec. 2 Twp. 11S S. R. 16W  East  West

- NW - NW - NE Spot Location / QQQQ County: Ellis

330' Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

2310' Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8-5/8" Set at: 249' Cemented with: 200 Sacks

Production Casing Size: 4-1/2" Set at: 3547' Cemented with: 175 Sacks

List (ALL) Perforations and Bridgeplug Sets: 2894-92, CIBP - 3124'; 3158-71'; CIBP 3190'; 3216-3304; CIBP - 3320'

Elevation: 2070 ( G.L. /  K.B.) T.D.: 3547' P.B.T.D.: 2303' Anhydrite Depth: 1265' (Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): in accordance with KCC rules and regulations

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? NA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Joel Stull

Phone: (785) 483-9169

Address: P.O. Box 307 City / State: Natoma, KS 67651

Plugging Contractor: Allied Cementing Co., Inc. / Val Energy KCC License #: 5822 6/05

Address: P.O. Box 31, Russell, KS 67665-0031 Phone: (785) 483-2627 (Contractor's)

Proposed Date and Hour of Plugging (if known?): \_\_\_\_\_

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 6/24/04 Authorized Operator / Agent: WR Henry (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

# WELL RECORD

RECEIVED

JUN 28 2004

KCC WICHITA

*KU 701-W*

Company Cities Service Oil Co. Well No. 1 Farm Cish "C"  
 Location 330' South and 330' East of N/4 Corner Sec. 2 T. 11 R. 16W  
 Elevation 2070 (2068 Cr.) County Ellis State Kansas  
 Drlg. Comm. December 16, 1948 Contractor Holm Drilling Company  
 Drlg. Comp. December 30, 1948 Acid See Below  
 T. D. 3547' Initial Prod. Physical Potential: 205 oil, 73 water, 24 hrs. (4-13-49)  
 P. D. 3448'

CASING RECORD:

8-5/8" @ 249' cem. 200 sx cement  
 4-1/2" @ 3547' cem. 175 sx cement

FORMATION RECORD:

shale & lime	0-40
lime	65
shale & shells	1000'
shale, shells & red bed	1225
anhydrite	1265
shale & shells	1350
shale & salt	1600
shale & shells	1840
lime & shale	2535
shale & lime	2810
lime & shale	3067
lime	3549

3549 RTD = 3547 SLM

Corr. Top Lensing 3240'  
 Penetration 307'  
 Total Depth 3547'

Drilled cement to 3534 SLM.

Perf. 24 shots 3453-61	}	<i>squeezed</i>
" 22 shots 3340-48		
" 24 shots 3328-36		
" 23 shots 3216-24		

Set retainer at 3192 and squeezed w/ 150 sacks cement; 127 sx through perfs. 3216-3461 at 1500#.

Drilled cement to 3260; no cement below 3260; hole making 2 gals. wtr. per hr. from perfs. 3328-3461.

Set packer at 3364 and tried to acidize 3453-61 w/ 500 gals., would not take acid. Acidized 3328-48 with 980 gals. Swabbed 79 1/2 water in 7 hrs.

Set retainer at 3183 and squeezed with 175 sx cement, 128 sx through perfs. 3328-3461 at 2500#.

Drilled cement and cleaned out to 3534 SLM.

Perf. 34 shots 3520-30	}	<i>squeezed</i>
" 23 shots 3504-10		
" 46 shots 3430-44		
" 30 shots 3404-14		
" 48 shots 3356-68		

2-11-49 Acidized 1000 gals. 3504-30  
 " Acidized 1000 gals. 3430-44  
 " Acidized 1000 gals. 3356-3414  
 2-14-49 Pumped 20 oil, 409 wtr., 19 hrs.

Set retainer at 3311 and squeezed w/ 200 sx cement, 170 sx through perfs. 3356-3520 at 2500#.

Drilled cement to 3448 SLM.

Perf. 47 shots 3292-3304	}	<i>2000 Gal.</i>		
" 46 shots 3272-85				
" 24 shots 3242-48			}	<i>1000 Gal.</i>
" 21 shots 3216-22				

3-7-49 Acidized 2000 gals. 3272-3304  
 " Acidized 1000 gals. 3216-48  
 3-10-49 Pumped 130 oil, 44 water, 9 hrs.

SYFO: 500 & 1000', 1°  
 1500, 2000, 2500, & 3000', 0°

7-7/8" rotary hole.

# KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor   Brian J. Moline, Chair   Robert E. Krehbiel, Commissioner   Michael C. Moffet, Commissioner

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Vess Oil Corporation  
8100 E. 22nd N. Bldg. 300  
Wichita, KS 67226

July 02, 2004

Re: GISH C #1  
API 15-051-05016-00-00  
NWNWNE 2-11S-16W, 330 FNL 2310 FEL  
ELLIS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #4  
2301 E. 13th  
Hays, KS 67601  
(785) 625-0550

Sincerely

  
David P. Williams  
Production Supervisor