

RECEIVED

JUL 23 2004

KCC WICHITA

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION

130 S. Market, Room 2078
Wichita, Kansas 67202

FORM CP-1

Rev. 03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API #: 15-113-21293-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date

6/05

WELL OPERATOR: American Energies Corporation (owner/company name) KCC LICENSE # 5399 (operator's)

ADDRESS: 155 North Market CITY: Wichita

STATE: Kansas ZIP CODE: 67202 CONTACT PHONE: 316-263-5785

LEASE: Otte WELL#: A #1 Section 33 Township 20 Range 1W

70'S of W/2 W/2 SW SPOT LOCATION/QQQQ COUNTY: McPherson

1250' FSL FEET (in exact footage) FROM South LINE OF SECTION (NOT Lease Line)

330' FWL FEET (in exact footage) FROM West LINE OF SECTION (NOT Lease Line)

Check One:	Oil Well _____	Gas Well _____	D&A _____	X _____	SWD/ENHR WELL _____	Docket # _____
	CONDUCTOR CASING SIZE _____	SET AT _____	CEMENTED WITH _____	SACKS _____		
	SURFACE CASING SIZE <u>8 5/8"</u>	SET AT <u>292'</u>	CEMENTED WITH _____	<u>200</u>	SACKS _____	
	PRODUCTION CASING SIZE _____	SET AT _____	CEMENTED WITH _____	_____	SACKS _____	

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:
ELEVATION 1514 G.L. 1519 K.B. T.D. _____ P.B.T.D. _____ Anhydrite Depth _____
(Stone Corral Formation)

CONDITION OF WELL: GOOD XX POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING:
Ran 4 1/2" drill pipe to 3050', brake circulation, mix to pump 35 sx 60/40 poz with 4% gel and disp. Pulled 4 1/2" drill pipe up to 332', brake circulation, mix to pump 65 sx 60/40 poz 4% gel and disp. Pulled 4 1/2" drill pipe up to 60'. Mix and pump 25 sx 60/40 poz 4% gel to surface. Ran 4 1/2" drill pipe in rat hole. Mix and pump 15 sx 60/40 poz 4% gel to surface and cement stayed in collar.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ Yes (YES,NO) IS ACO-1 FILED? Yes (YES,NO)
If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Name: Alan L. DeGood, President Phone#: (316) 263-5785

Address: 155 North Market, Suite 710 City: Wichita State: Kansas

PLUGGING CONTRACTOR: United Cementing and Acid Co., Inc. KCC LICENSE #: 30437
(company name) (contractor's)

Address: 2510 West 6th Street City: Eidorado State: Kansas Zip 67042

PROPOSED DATE AND HOUR OF PLUGGING (if Known?) 6/30/04 6:30 a.m. Plugged
PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY: _____ Operator X Agent _____

DATE: 07/07/04 AUTHORIZED OPERATOR OR AGENT: Alan L. DeGood
(signature) Alan L. DeGood, President

9/04