

**KANSAS CORPORATION COMMISSION RECEIVED**  
**OIL & GAS CONSERVATION DIVISION**  
**WELL PLUGGING APPLICATION JUL 21 2004**  
*Please TYPE Form and File ONE Copy* **KCC WICHITA**

Form CP-1  
 September 2003  
 This Form must be Typed  
 Form must be Signed  
 All blanks must be Filled

API # 15 - 051-2076300 - 00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 9-17-1971.

Well Operator: M.E. Klein & Associates, Inc. KCC License #: 31933  
(Owner / Company Name) (Operator's)

Address: 1818 West Lindsey Bldg C-180 City: Norman  
 State: OK Zip Code: 73070 Contact Phone: (405) 627 - 0669

Lease: Herl Well #: 4 Sec. 35 Twp. 14 S. R. 19  East  West  
 C - SW - ne - NW 1/4 Spot Location / QQQQ County: Ellis Ks

4290 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)  
3630 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8 5/8ths Set at: 1375 Cemented with: 600 sks Sacks

Production Casing Size: 5 1/2 Set at: 3658 Cemented with: 100 sks Sacks

List (ALL) Perforations and Bridgeplug Sets: LKC 3559-3566 LKC 3599-3612

Elevation: 2111 ( G.L. /  K.B.) T.D.: 3762 PBDT: N/A Anhydrite Depth: 1368  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Plugging orders by Hays District Office Jay Pfeifer Field agent  
1st plug @ 2000' 100sks 60/40 10% gell 4sks hulls 2nd plug @ 1375' 30 sks 60/40 10% gel 2sks hulls 3rd plug @ 675'  
70sks 60/40 10% gel 2sks hulls 4th circulate with 50sks 60/40 10%gel plugging complete.

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

**Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.**

List Name of Company Representative authorized to be in charge of plugging operations: \_\_\_\_\_  
Carl Zimmerman Phone: (785) 635 - 0692

Address: 1116 East 8th St City / State: Hays, Kansas.

Plugging Contractor: Allied Cementing KCC License #: 99996  
(Company Name) (Contractor's)

Address: Russell Ks. Phone: (785) 625 - 3019

Proposed Date and Hour of Plugging (if known?): within 60 days.

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 7-14-04 Authorized Operator / Agent: *Carl Zimmerman*  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

# KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    Robert E. Krehbiel, Commissioner    Michael C. Moffet, Commissioner

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

M E Klein & Associates, Inc  
PO Box 721436  
Norman, OK 73070-8106

July 29, 2004

Re: HERL #4  
API 15-051-20763-00-00  
SWNENW 35-14S-19W, 4290 FSL 3630 FEL  
ELLIS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #4  
2301 E. 13th  
Hays, KS 67601  
(785) 625-0550

Sincerely  


David P. Williams  
Production Supervisor