

RECEIVED
JUL 15 2004
KCC WICHITA

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-155-20125-00-02 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date. 2/05

WELL OPERATOR Whitetail Crude, Inc KCC LICENSE # 31627
(owner/company name) (operator's)

ADDRESS P O Box 544 CITY Ness City

STATE KS ZIP CODE 67560-0544 CONTACT PHONE # (785) 798-3641

LEASE Dion OWWO WELL# 1 SEC. 3 T. 23S R. 10W (East/West)

NE NW SW SPOT LOCATION/OQQQ COUNTY Reno

2310 FEET (in exact footage) FROM S/~~XX~~ (circle one) LINE OF SECTION (NOT Lease Line)

990 FEET (in exact footage) FROM E/~~W~~ (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 253 CEMENTED WITH _____ SACKS

PRODUCTION CASING SIZE 4 1/2 SET AT 3770 CEMENTED WITH 200 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3222-32, 3351-56, CIBP @ 3320

ELEVATION 1759 T.D. 3774 PSTD 3320 ANHYDRITE DEPTH _____
(G.~~XX~~/K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Sand off 4 1/2 casing to 50' above perms (3290), spot 4 sks cement thru dump bailer, shoot off 4 1/2 casing @ 2500', pull casing to 1400', pump 35 sk plug @ 1400', pull to 900', pump 35 sk plug, pull to 250'; circulate cement to surface, lay down rest of 4 1/2 & top off 8 5/8 to surface. 60-40 poz 6% gel cement
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? no IS ACO-1 FILED? yes

If not explain why? no logs received from Blue Ridge Petroleum Corp

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Mike J. Fritzler, President PHONE# () 785-798-3641

ADDRESS P O Box 544 City/State Ness City, KS 67560-0544

PLUGGING CONTRACTOR Whitetail Crude, Inc KCC LICENSE # 31627
(company name) (contractor's)

ADDRESS P O Box 544, Ness City, KS 67560-0544 PHONE # () 785-798-3641

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) ASAP

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 7/14/04 AUTHORIZED OPERATOR/AGENT: Mike J. Fritzler
(signature)
Mike J. Fritzler, President

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Whitetail Crude, Inc
N Hwy 283
PO Box 544
Ness City, KS 67560-544

July 19, 2004

Re: DION #1
API 15-155-20125-00-02
NENWSW 3-23S-10W, 2310 FSL 990 FWL
RENO COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely



David P. Williams
Production Supervisor

District: #2
130 S. Market, Room 2125
Wichita, KS 67202-3208
(316) 337-6231