

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

Please TYPE Form and File ONE Copy

15-073-19056-00-01

API # 15-207-22,317 ^{WAGON COUNTY} ~~CANCELLED API~~ _{10/29/04} (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 9-18-80

Well Operator: CROSS OIL, L.L.C. (Owner / Company Name) KCC License #: 32044 (Operator's)

Address: BOX 94 City: HAMILTON

State: KS Zip Code: 66853 Contact Phone: (620) 678 - 3813

Lease: DINIUS Well #: 40 Sec. 31 Twp. 24 S. R. 13 East West

SW1/4 - SW31 - 24S - 13E Spot Location / QQQQ County: GREENWOOD

660 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

660 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # E-4497 ENHR Docket # _____ Other: INJECTION WELL

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 7" Set at: 44' Cemented with: 10 Sacks

Production Casing Size: 4 1/2" Set at: 1615' Cemented with: 50 Sacks

List (ALL) Perforations and Bridgeplug Sets: BARTLESVILLE -1631-1649

Elevation: 1056' (G.L. / K.B.) T.D.: 1715' PBTD: _____ Anhydrite Depth: _____ (Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): UNABLE TO FISH FIBERGLASS TUBING OUT OF HOLE, STATE PLUGGER ADVISED TO SHOOT HOLES @ 700' SET ROCK BRIDGE ON TOP OF TUBING, MIX & DUMP 10 SACKS OF CEMENT, UNSCREW CASING @ 150', SET BRIDGE & FILL WITH CEMENT TO SURFACE.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

RECEIVED
JUN 23 2004
KCC WICHITA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: DENNIS SMITH

Phone: (620) 678 - 3813

Address: BOX 94 City / State: HAMILTON, KS

Plugging Contractor: CROSS OIL, L.L.C. (Company Name) KCC License #: 32044 (Contractor's)

Address: BOX 94 HAMILTON, KS 66853 Phone: (620-) 836 - 5803

Proposed Date and Hour of Plugging (if known?): AS SOON AS POSSIBLE 6-25-04 Plugged

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 6-22-04 Authorized Operator / Agent: Dennis Smith (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202