

State of Kansas



15-147-20232-60-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 24 1978
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Wagner of Red Tiger Drlg. has this

date requested permission to plug the following described well:

Mr. Wagner guarantees payment of the plugging fee.

Operator's full Name: American Petroleum Co., Inc.

Complete Address: Suite 111-400 N. Woodlawn, Wichita, Kansas

Lease Name: Dill "D" Well No. 1A

Location: NW NW SE Sec. 13 Twp. 3 Rge. (E)(W) 19

County: Phillips Total Depth 3425' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Wagner was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 900' thru drill
pipe. Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy
mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Lee M. Moseley
Conservation Division Agent