

State of Kansas



15-147-20244-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT - 5 1978
10-5-78
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Moore of Pioneer Drlg. has this
date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: PMI, Inc.

Complete Address: 400 N. Woodlawn, Wichita, Ks.

Lease Name: Veeh Well No. 2

Location: 100' N of NW SE SE Sec. 26 Twp. 3 Rge. (E)(W) 19

County: Phillips Total Depth 3418' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Moore was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 900' thru drill

pipe. Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Leo Massey
Conservation Division Agent