

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 147-20, 266-00-00 (of this well)

Operator's Full Name TERRA RESOURCES INC.

Complete Address P.O. Box 839 OKLAHOMA CITY, OKLAHOMA 73101

Lease Name PILLMORE Well No. #1

Location Q-SW-SE-SW Sec. 21 Twp. 3 Rge. 17 (E) (W) W

County PHILLIPS Total Depth 3808 FE.

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated GOT DRILL COLLARS + DRILL PIPE STUCK - LAST HOLE

Plugging Contractor EMPHASIS OIL OPERATIONS

Address BOX 506 RUSSELL, MISS. - 64665 License No.

Operation Completed: Hour 4:00 PM Day 6th Month FEB Year 1980

The above well was plugged as follows:

8 5/8" 759 FE SD. CUC. w/425 ST 60/140 POZMIX 2% GEL - 3% CA-CL.

EMPHASIS STUCK AND LOST 257 FE DRILL COLLARS AND 1800 FE DRILL PIPE IN HOLE
FISH AT 1384 FE

ORDERED 105 ST 50/150 POZMIX 6% GEL - + 8 5/8 PLUG. (Elev. 1950) ^{KB.}

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1ST PLUG. @ 850 FE w/40 ST cmt

2ND PLUG. @ 420 FE w/20 ST cmt.

3RD PLUG. ^{SOLID BRIDGE} HULL'S PLUG. @ 40 FE 0 w/10 ST cmt 5ST EMERIT

I hereby certify that the above well was plugged as herein stated.

Signed: Marion J. Schmitt
Well Plugging Supervisor
Wichita, Kansas

RECEIVED
CORPORATION COMMISSION
WICHITA, KANSAS
FEB 13 1980

INVOICED

DATE 2-14-80

INV. NO. 1519-w

02-13-1980