

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 25 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-147-20094-00-00

Operator's Full Name Petroleum Mangement, Inc.

Complete Address 1515 KSB&T Bldg, Wichita, Kansas

Lease Name Gower Well No. 1

Location NE NE NE Sec. 8 Twp. 3 Rge. (E) (W) 16

County Phillips Total Depth 3784'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Red Tiger

Address Wichita, Kansas License No.

Operation Completed: Hour 3:30A Day 21 Month 5 Year 1970

The above well was plugged as follows:

RTD 3784' 8 5/8 csg set at 215' cwc Cmt. Mat. 50-50 poz cmt W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 900' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Paul W. Massey
Well Plugging Supervisor

INVOICED
DATE 5/25/70
INV. NO. 1934-11