

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
Form CP-3  
Rev. 6-1-68  
STATE CORPORATION COMMISSION

SEP 07 1976  
9-7-76  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 -147 -19078-00-00 (of this well)

Operator's Full Name Petroleum Management, Inc.

Complete Address P. O. Box 1325, Great Bend, Kansas 67530

Lease Name Miller Well No. 203

Location NW SW NE Sec. 13 Twp. 3 Rge. (E) (W) 19

County Phillips Total Depth 3357'

Abandoned Oil Well        Gas Well        Input Well XX SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Co. Tools by Halliburton Cementing Co.

Address        License No.       

Operation Completed: Hour 11:15 A Day 2 Month 9 Year 1976

The above well was plugged as follows:

Total Depth 3357' . 8 5/8 csg set 231' cwc

5 1/2 csg set 3357' cw 120 sx cem 2-stage 1550' W/400 sk. No pipe recovered.

Halliburton Cementing Co. mixed & pumped down 5 1/2 csg with 70 sk Comm Cem -200 lbs

hulls W/25 sk gel & water -released 5 1/2 plug & 30 sk Comm Cem. FPP 550 lbs.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Reo Massey  
Well Plugging Supervisor

DATE 9/7/76

INV. NO. 3775-W