

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-147-00892-00-00

RECEIVED
STATE CORPORATION COMMISSION
AUG 22 1974
8-22-74
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum Management, Inc.
Complete Address Box 1325, Great Bend, Kansas 67530
Lease Name Miller "A" Well No. 2
Location NW NW SW Sec. 13 Twp. 3 Rge. (E) (W) 19
County Phillips Total Depth 3562'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Co. Teels
Address License No.
Operation Completed: Hour 10:30 A Day 20 Month 8 Year 1974

The above well was plugged as follows:

Total Depth 3562' 8 5/8 esg set at 1504' cew

5 1/2 esg set at 3368' cw 250 sk cem.

5 1/2 esg perf. (3110')

Filled 5 1/2 esg W/sd to 3000' & dumped 4 sk cem W/dump bailer. (2900-2970)

Cutoff and recovered 2272' of 5 1/2 esg.

Filled 8 5/8 esg with mud to 775' -set rock & sand bridge (775-760)

Filled with RMC (760-400) dumped 15 bbl water to 170'

Set rock & sand bridge (170-160) & filled to base of cellar with RMC. (160-0)

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/22/74

INV. NO. 9755-W

Signed: Leo J. Massey
Well Plugging Supervisor