

DISTRICT CONSERVATION AGENT'S REPORT

15-147-19083-00-00

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 67-4

LOCATION NE SE NE

SEC. 14 TWP. 3 RGE. 19

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Vogel

Operator Imperial Pet Co Address Wichita, Kans

Field _____ County Phillips

Total Depth 3182 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 152' circulated with cement - 5 1/2" at 317' with
100 sax cement behind. Perforations at 3140'.

Filled with sand to 3130', set 4 sax cement with dump bailer,
pulled 2000' 5 1/2", mud to 152', set rock and 15 sax cement,
mud to 35', set rock and 10 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION

JAN 2 - 1953

CONSERVATION DIVISION
Wichita, Kansas

Edmund [Signature]
District Conservation Agent

Date 12-28-52

PLUGGING

FILE SEC 14 3 R 19
BOOK 67 PAGE 4

1-2-53