

DISTRICT CONSERVATION AGENT'S REPORT

15-147-00896-00-00

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 07-0  
LOCATION SW SE NE  
SEC. 14 TWP. 5 RGE. 19

Dry Hole \_\_\_\_\_ Abandoned Oil Well  Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 4 Lease Petr Vogel 903 UNB Bldg  
Operator Imperial Drg Co. INC Address Wichita, Kans  
Field \_\_\_\_\_ County Phillips  
Total Depth 5227 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 175' circulated with cement - 5 1/2" at 5227' with  
125 sax cement behind - perforations at ~~2120~~ 2138'  
Filled with sand to 3120', set 4 sax cement with dump bailer  
pulled 2230' 5 1/2" - filled with mud to 175', set rock and  
15 sax cement - mud to 55', set rock and 10 sax cement to  
bottom cellar.

**PLUGGING**  
FILE SEC 14 T 3 R 19  
BOOK PAGE 67 LINE 6

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 13 1953  
CONSERVATION DIVISION  
Wichita, Kansas

District Conservation Agent  
Date 1-6-53

1-10-53