

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 147 - 20,221 000 10-8-76
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Lorell Keesee
Complete Address 797 3rd St., Phillipsburg, Kansas
Lease Name Keesee Well No. 1
Location C NW NE SW Sec. 23 Twp. 3 Rge. (E) (W) 19
County Phillips Total Depth 3225'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Abercrombie Drlg.
Address Wichita, Kansas License No.
Operation Completed: Hour 1:30 P Day 6 Month 10 Year 1976

The above well was plugged as follows:

RTD 3225' 8 5/8 csg set 212' cwc 150 sx. Plg. Mat. 50-50 poz 6% total gel.
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 900' thru drill pipe.

Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Massey
Well Plugging Supervisor

INVOICED

DATE 10-8-76

INV. NO. 3961-W