

15-147-00940-00-00
DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION SE NE SW

SEC. 23 TWP. 3 RGE. 19 W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease _____ Ehm 702 Un. Center

Operator Thunderbird Drg Co Inc, Address Wichita, Kans

Field _____ County Phillips

Total Depth 3372 Feet.

Plugging Contractor Forbes Casing Pulling

Plugging Contractor's License No. 49

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 214' circulated with cement - 5 1/8" at 3372' with 100
sax cement behind - perforated at 3133'.

Filled with chat to 3120', set 4 sax cement with dump bailer,
pulled 2025' 5 1/2" - filled with mud to 210', set rock and 15 sax
cement, mud to 35', set rock and 10 sax cement to bottom cellar.

Edward Kelly
District Conservation Agent

Date 10-31-56

PLUGGING
FILE SEC 23 T. 3 R. 19W
BOOK PAGE 113 LINE 26

RECEIVED
STATE CORPORATION COMMISSION
NOV - 5 1956
CONSERVATION DIVISION
Wichita, Kansas
15-56