

DISTRICT CONSERVATION AGENT'S REPORT

15-147-00672-00-00

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 24-15

LOCATION SW NW NE

SEC. 23 TWP. 3 RGE. 19

Dry Hole Abandoned Oil Well Abandoned Gas Well

I have today completed supervision of plugging of:

Well No. 4 Lease Hempler

Operator Phillips Pet Co Address Great Bend, Kans

Field _____ County Phillips

Total Depth 3363 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 278' circulated with cement - 5 1/2" at 3363'

with 150 sax cement behind, perforated at 1513 and squeezed

with cement from 1513 to 0' with cement.

Pumped in 30 sax Aquagel filling hole with mud, pumped

cementing plug to 290', filled with cement 290' to 0'

at 200# pressure (cementing and mudding by Halliburton Co)

RECEIVED
STATE CORPORATION COMMISSION

JUN 26 1952

CONSERVATION DIVISION
Wichita, Kansas Date

Edward J. [Signature]
District Conservation Agent

6-20-52

626-52