

DISTRICT CONSERVATION AGENT'S REPORT

15-147-00166-00-00

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 72-43

LOCATION SE SW SE

SEC. 15 TWP. 3 RGE. 19

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. A-1 Lease \_\_\_\_\_ Miller \_\_\_\_\_

Operator Derby Oil Co Address Wichita, Kans

Field \_\_\_\_\_ County Phillips

Total Depth 3463 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 156' circulated with cement - 4 1/2" at 3461' with  
125 sax cement behind - Lane Wells plugs to 3284' top perforation  
at 3270' .

Filled with chat to 3260', set 4 sax cement with dump bailer,  
pulled approximately 2600', 4 1/2", filled hole with mud to 155',  
set rock and 15 sax cement, filled hole to 35', set rock and 10  
sax cement to bottom cellar.

**PLUGGING**  
FILE SEC. 15 T 3 R 19  
BOOK PAGE 77 LINE 43

District Conservation Agent

Date

5-1-51

**RECEIVED**  
STATE CORPORATION COMMISSION

MAY 4 - 1951

CONSERVATION DIVISION  
Wichita, Kansas

54-51