

15-147-00889-00-01

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 12 1961

CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Phillips
Location: SW NW NW Sec. 13 Twp. 3 Rge. 19 (E) (W)
Name of Field: _____ Total Depth: 3390

I have this date completed supervision of plugging of:

Lease Name: Stuttgart Unit Well No. 1

Operator's Full Name: Phillips Pet Co

Complete Address: Box 779 Great Bend, Kans

Plugging Contractor: Knight Casing Pulling

Address: Great Bend, Kans License No. 436

See
Per 074

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 3PM Day 7 Month 5 Year 61

The above well was plugged as follows:

8 5/8" 289' circulated with cement - 5 1/2" 3390' with 150 sax cement - PB
3362' - Perf 3135'.

Filled with sand to 3135', set 5 sax cement with dump bailer, pulled 1510'
5 1/2" to 500', circulated hole with heavy mud through 5 1/2" at 500' (17 sax Gel)
displaced 20 sax cement through 5 1/2" at 500', heavy mud to 190', displaced
20 sax cement through 5 1/2" at 190', heavy mud to 35', set bridge and 10 sax
cement to bottom cellar.

Mudding and cementing by Knight Co pump truck.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED

DATE 5/19/61
INV. NO. 3140-W

RECEIVED
STATE CORPORATION COMMISSION
MAY 12 1961
CONSERVATION DIVISION
Wichita, Kansas