

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 24 1978
424-78
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 147- 20,232-0200 (of this well)

Operator's Full Name Americam Petroleum Co., Inc.

Complete Address Suite 111-400 N. Woodlawn, Wichita, Kansas

Lease Name Dill "D" Well No. 1A

Location NW NW SE Sec. 13 Twp. 3 Rge. (E) (W) 19

County Phillips Total Depth 3425'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Red Tiger Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 1:15 P Day 22 Month 4 Year 1978

The above well was plugged as follows:

RTD 3425' 8 5/8 csg set 213' cwc 150 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 900' thru drill pipe.

Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I, hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 4-26-78

INV. NO. 7174-0