

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

15-147-00158-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 13 1962  
CONSERVATION DIVISION  
Wichita, Kansas  
10-16-62

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Don H. Peaker

Complete Address: Box 1595 Pueblo, Colorado

Lease Name Veeh Well No. 1

Location NW NW SE Sec. 26 Twp. 3 Rge. (E) (W) 19

County Phillips Total Depth 3407

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated: wash down

Plugging Contractor: Barnes & Sons

Address: Russell, Kans License No. 9

Operation Completed: Hour 5PM Day 8 Month 10 Year 62

The Above well was plugged as follows:

8 5/8" 225' circulated with cement - 4 1/2" at 3404' with 225 sax cement  
PB to 3236', perf 3220' - filled with sand to 3210', set 4 sax cement with  
dump bailer-

Pulled 1192' 4 1/2" to 550', circulated hole with heavy mud through 4 1/2" ( 23  
sax gel), displaced 20 sax cement through 4 1/2" at 550', heavy mud to 190'  
displaced 20 sax cement through 4 1/2" at 190', heavy mud to 35', set bridge  
and 10 sax cement to bottom cellar.

Mudding and cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

Signed: Edon Pett  
Well Plugging Supervisor

INVOICED

DATE 10/18/62

INV. NO. 5852-u