

15-147-00072-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 61-41

LOCATION NW NW NW

SEC. 24 TWP. 3 RGE. 19

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Deikhoff Dieckhoff

Operator Westgate Greenland Oil Address Wichita, Kans

Field _____ County Phillips

Total Depth 3261 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 194' circulated with cement - 5 1/2" at 3236' with
75 sax cement behind - Lane Wells Plugs to 3232' - top perf.
at 3220' -

Filled with chat to 3210', set 4 sax cement with dump bailer,
pulled 2700' 5 1/2", filled hole with heavy mud to 190', set
rock bridge and 15 sax cement, filled with heavy mud to 35',
set rock bridge and 10 sax ~~cement~~ cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING MAR 31 1951
FILE SEC 24 T 3 R 19 CONSERVATION DIVISION
Wichita, Kansas
BOOK PAGE 64 LINE 4

J. P. [Signature]
District Conservation Agent

Date 3-23-51

3-31-51