

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

AUG 28 1974

CONSERVATION DIVISION  
Wichita, Kansas

8-28-74

15-147-00900-00-00  
01

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Petroleum Management, Inc.

Complete Address P. O. Box 1325 Great Bend, Kansas 67530

Lease Name Vogel Well No. 1

Location NE NE SE Sec. 14 Twp. 3 Rge. (E) (W) 19

County Phillips Total Depth 3550'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Co. Tools

Address Wichita, Kansas License No. 731

Operation Completed: Hour 3:30 P Day 27 Month 8 Year 1974

The above well was plugged as follows:

Total Depth 3550' 8 5/8 csg set at 1507' cwc 875 sk.

5 1/2 csg set at 3354' cw 150 sx cem.

5 1/2 csg perf. (3114-3124)

Set 5 1/2 wood plug at 3000' -poured 20' sand -dumped 4 sk cem W/dump bailer. (3000-2950)

Cutoff and recovered 2408' of 5 1/2 csg.

Filled 8 5/8 csg W/mud to 800' -set rock & sand bridge (800'-775')

Filled with RMC (775'-400') Filled W/mud (400'-170')

RMC from 170' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/29/74

INV. NO. 9790-U

Signed: Leo G. Messing  
Well Plugging Supervisor

ZDR  
CP-1, CP-2  
KAC-000  
8-3-74