

15-147-00888-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

			#

Locate well correctly on above  
Section Plat

Phillips County, Sec. 11 Twp. 38 Rge. 19 (E) W (W)  
 Location as "NE/CNWxSWx" or footage from lines. NE NE  
 Lease Owner Humble Oil & Refining Co.  
 Lease Name Estistle Well No. 1  
 Office Address 2000 Classen Center-North Bldg., Oklahoma City, Okla.  
 Character of Well (completed as Oil, Gas or Dry Hole) Oil  
 Date well completed \_\_\_\_\_ 19\_\_\_\_  
 Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
 Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
 Plugging commenced Nov. 6, 1967  
 Plugging completed Nov. 8, 1967  
 Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	281'	None
				5 1/2	3304'	1220'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back with sand from 3316' to 2980'. Mixed and dumped 5 sx. of cement from 2980' to 2940'. Pulled casing.  
 Mixed and pumped in 25 sx. of gel mud. Mixed and pumped in 100 sx. of cement from 570' to 270'. Mixed and pumped in 10 sx. of gel mud from 270' to 75'. Mixed and pumped in 15 sx. of cement from 75' to base of the cellar.

RECEIVED

NOV 22 1967

CONSERVATION DIVISION  
Wichita, Kansas

11-22-67

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Russ Casing Pulling Inc.  
 Address Box 1082 Great Bend, Ks.

STATE OF Kansas, COUNTY OF Russell, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Allen J. Underwood

SUBSCRIBED AND SWORN TO before me this 21<sup>st</sup> day of November, 1967

(Address) Velma Underwood

My commission expires September 27, 1971

Notary Public.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg. Wichita, Kansas.

COPY


CARTER OIL CO.  
August Eltiste No. 1.

SEC 11 T. 3 R. 19 W  
CNE NE  
660' F NL 660' F EL NE  $\frac{1}{4}$

15-147-00888-00-00

Total Depth. 3308  
Comm. 6-30-42 Comp. 7-27-42  
Shot or Treated.  
Contractor. Crow Drilling Co.  
Issued. 10-17-42

County Phillips.



CASING.

85/8" 287'  
5 1/2" 3304'

Elevation.

Production. Pot. 50 B.  
pump.

Figures Indicate Bottom of Formations.

surface clay 35  
shale & shells 287  
shale 293  
shale & shells 705  
sand 738  
shale sand strks 860  
sand 908  
shale & shells 920  
sand and shale 1439  
shale 1507  
anhydrite 1531  
shale 1558  
shale & shells 1785  
shale & shells 1921  
shale & limo strks 2268  
shale & broken  
lime 2355  
shale, broken lime  
streaks 2403  
limo sdy 2420  
limo and shale 2490  
broken lime 2567  
shale and limo 2707  
shale 2752  
limo 2784  
limo 2796

broken lime 2875  
lime and shale 3022  
lime 3308  
Total Depth.

Top Topeka 2890  
Top K.C. 3116

Slight Porosity ~~air~~ show oil 3116-19  
Slight Porosity fair show oil 3185-91  
Slight porosity S.S.O. 3227-30  
slight por. with fair sh oil 3304-07

RECEIVED  
THE CORPORATION COMMISSION  
SEP 19 1967  
9-19-67  
CONSERVATION DIVISION  
Wichita, Kansas