


15-147-00128-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Phillips County, Sec. 28 Twp. 3S Rge. 18 ~~XXX~~ (W)

Location as "NE/CNW/SW" or footage from lines Center of NW-NW-NE

Lease Owner Amerada Petroleum Corporation

Lease Name Louise Morgan Well No. 1

Office Address Box 197 - Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 8-28-58 1958

Application for plugging filed 8-28-58 1958

Application for plugging approved _____ 19____

Plugging commenced 1:30 PM 8-28-58 1958

Plugging completed 2:45 PM 8-28-58 1958

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3668 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1305'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Halliburton Spotted Plugs @ 500' W/20 Sax Cement
@ 185' W/15 Sax Cement
@ 40' W/ 1/2 Sax Cottonseed Hulls & 10 Sax Cement.
Finished @ 2:45 PM 8-28-58.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Peel Brothers Inc.

Address Box 88 - Hoisington, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Clifford E. Richardson (employee of owner) ~~XXX (owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clifford E. Richardson

Box 197 - Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of August, 19 58

Charles W. Anderson
Notary Public.

My commission expires November 21, 1961

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC. 28 T. 3 R. 18 W
BOOK PAGE 126 LINE 24

AUG 30 1958 8-30-58

CONSERVATION DIVISION
Wichita, Kansas

DRILLERS' LOG

Well Owner:	Amerada Petroleum Corporation	C NW NW NE
Farm Name:	Louise Morgan #1	Sec. 28-3S-18W
Commenced:	8/17/58	Phillips County, Kansas
Completed:	8/28/58	Elevation:
Total Depth:	3668'	Production: Dry
Casing:	8 5/8" @ 1306' cemented	
Contractor:	Peel Brothers, Inc.	

Figures below indicate bottoms of formations

Clay	0	160
Shale		860
Sand		920
Shale		1330
Red bed		1550
Sand		1680
Shale		1785
Red bed		2060
Red bed and shale		2325
Shale		2575
Shale and lime		2690
Shale		3040
Lime and shale		3120
Lime		3550
Lime and shale		3605
Chert		3639
Arbuckle		3668
Total Depth		3668

This is to certify that the above information is to the best of our knowledge, true and correct.

PEEL BROTHERS, INC.

BY *Frank Malloy*

SUBSCRIBED AND SWORN to before me this 29th day of August, 1958

My commission expires: April 27, 1960

Ruth Brant
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

SEP 6 1958 *9-6-58*

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 28 T 3 R 18W
BOOK PAGE 126 LINE 24