

15-147-0053-00-04

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Phillips SEC. 12 TWP. 3 RGE. 19W E/W
 Location as in quarters or footage from lines:

W/2 NW/4 450' S of N Line

Locate Well
 correctly on above
 Section Platt.

Lease Owner Don H. Peaker

Lease Name Kaiser #2 SWD Well No. _____

Office Address P.O. Box 1595 Pueblo, Colorado 81002

Character of Well (Completed as Oil, Gas or Dry Hole): _____

Date Well Completed _____

Application for plugging filed _____

Plugging commenced 8-19-82

Plugging completed 8-19-82

Reason for abandonment of well or producing formation _____

Depleted

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hammel

Producing formation _____ Depth to top _____ bottom T.D. 3368'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	160'	none
				5-1/2"	3367'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged Only, No Pipe Recovery: Pumped 3 sacks hulls and 125 sacks cement down 8-5/8" surface pipe. Pumped 2 sacks hulls, 50 sacks cement, 16 sacks gel, 2 sacks hulls and 100 sacks cement, 50/50 pos, 6% gel, 3% cc down 5-1/2" long string.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

R. Darrell Kelso
 Box 347 Chase, Ks. 67524
 (Address)

SUBSCRIBED AND SWORN TO before me this 22nd. day of September, 19 82

My Commission expires:



RECEIVED
 STATE CORPORATION COMMISSION

SEP 23 1982
 CONSERVATION DIVISION
 Wichita, Kansas

9-23-82

WELL LOG 15-147-00153-00-00

COMPANY **Lewis Drilling Co., etal**

SEC. 12 T. 3 R. 19W
 LOC. **1/4 NW 1/4 - 450' S. of N. Lane**
400' E. of W. Lane

FARM **Kaiser** NO. **2**

TOTAL DEPTH **3368**
 COMM. **2-18-57** COMP. **3-3-57**

COUNTY **Phillips**
KANSAS

SHOT OR TREATED
 CONTRACTOR **Lewis Drilling Company**
 ISSUED

CASING

20	10	
15	8 1/2"	= 160'
12	6	
13	5 1/2"	= 3367'

ELEVATION **2004 K.B.**

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0-30
 30-50
 50-500
 500-1192
 1192-1520
 1520-3368
 3368

Surface soil
 Post rock
 Shale
 Sand and shale
 Anhydrite
 Lims & shale
 Total Depth

Geologic Tops


Heebner	3058
Toronto	308 1/2
Lansing KC	3100
Base Kansas City	3312

RECEIVED
 STATE CORPORATION COMMISSION
APR 29 1982
 CONSERVATION DIVISION
 Wichita, Kansas
 4-29-82

State of Kansas }
 County of Sedgwick } SS:

I, J. Fred Hambright of the Lewis Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Kaiser #2 well.



Subscribed and sworn to before me this 6 day of March 19 57

J. Fred Hambright

My Commission Expires: 8-20-60

A. R. Darrington
 A. R. Darrington NOTARY PUBLIC