

15-147-00046-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

OR

Phillips County. Sec. 9 Twp. 3S Rge. 19W (E) (W)  
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. NE SW SE  
Lease Owner. Denver Oil Company, Inc.  
Lease Name. Mueller Well No. 1  
Office Address. Phillipsburg, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole). Dry Hole  
Date well completed. September 12, 19 45  
Application for plugging filed. Sept. 12, (verbal) 19 45  
Application for plugging approved. September 18, 19 45  
Plugging commenced. September 12, 19 45  
Plugging completed. September 14, 19 45  
Reason for abandonment of well or producing formation. Dry Hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production. none 19  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well. H. W. Kerr  
Producing formation. Depth to top. Bottom. Total Depth of Well. 3578 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

The hole was filled with heavy mud from 3578 feet to bridge at 200 feet. 15 sacks of cement from 200 feet to 170 feet. Mud from 170 feet to 20 feet. 10 sacks of cement from 20 feet into base of cellar. 212 feet of 10 inch pipe cemented and left in hole.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. Denver Oil Company,  
Address. Phillipsburg, Kansas

STATE OF \_\_\_\_\_, COUNTY OF \_\_\_\_\_, ss.  
\_\_\_\_\_  
(employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) X \_\_\_\_\_ X

(Address)

SUBSCRIBED AND SWORN to before me this \_\_\_\_\_ day of \_\_\_\_\_, 19 \_\_\_\_\_

My commission expires \_\_\_\_\_

Notary Public.



Rec'D  
9-24-45

15-147-00046-00-00

# Denver Oil Company, Inc.

Denver VanDeventer, Pres.  
Howard D. Fink, Vice-Pres.  
H. A. Bethke, Treasurer  
Geo. H. Chamblin, Secretary

306 STATE STREET  
PHILLIPSBURG, KANSAS  
Phone Number 124

Well No. 1  
Farm Mueller  
Description NE SW SE 9-3S-19W  
County Phillips  
File: 26-16

## PLUGGING RECORD

Hole was filled from bottom up to 215 S.L.M. with heavy rotary mud.

1 plug set at 210 feet with 15 sacks cement on top of plug.

Hole then filled to 25 ft. with heavy rotary mud. Plug set with 10 sacks cement.

Signed:



Tool Pusher



9-24-45

15-147-00046-00-00

# Denver Oil Company, Inc.

Denver VanDeventer, Pres.  
Howard D. Fink, Vice-Pres.  
H. A. Bethke, Treasurer

September 20, 1945

STATE CORPORATION  
COMMISSION

SEP 24 1945

CONSERVATION  
DIVISION

306 STATE STREET  
PHILLIPSBURG, KANSAS  
Phone Number 424

Mr. H. W. Kerr  
Great Bend, Kansas

Dear Mr. Kerr:

Enclosed is our check to the State Corporation Commission for plugging assessment in the amount of \$25.00; also one copy of the bill as requested by them.

There is a note at the bottom of their remittance form as follows: "We also need a written application to plug, well log and plugging record covering this well, to complete this file."

Mr. H. R. Buick plugged our well, Miller #1, NE  $\frac{1}{4}$  SW  $\frac{1}{4}$  SE  $\frac{1}{4}$  9-3-19W, as per your instructions by phone. He has made out and we enclose herewith what we consider the necessary information to comply with the note at the bottom of their bill. He has suggested that we send this to you, and that if it is correct you will send it on to the Corporation Commission. If not, you will make the necessary changes and suggestions and return same to our office.

There is a question in our mind as to whether or not we should include with this report a well log. There is a further question whether a copy of the Schlumberger log and/or a copy of the regular well log should be sent to the Corporation Commission.

Use your own discretion in sending the material we forward to you to the Commission or in holding it until we have supplied anything you feel is missing.

Thanking you for your cooperation, we are

Very truly yours,

DENVER OIL COMPANY, INC.

*Denver VanDeventer*  
Denver VanDeventer, President

DV:lm  
Enc. 3

