

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-147-19002-00-01
A14719002000-1
API NUMBER SAUGHTON 1942R 1

LEASE NAME SOUTH KAISER

TYPE OR PRINT
NOTICE: Fill out completely
and return to Coas. Div.
office within 30 days.

WELL NUMBER 1

660 Ft. from S Section Line

660 Ft. from X Section Line

SEC. 1 TWP. 3 RGE. 19W (E) or (W)

COUNTY PHILLIPS

Date Well (Completed) AUG 10 1942

Plugging Commenced may 1 2001

Plugging Completed mat 1 2001

LEASE OPERATOR JOHNSON OIL

ADDRESS 258 east highway 36

PHONE (785) 543 6171 OPERATORS LICENSE NO. 3077

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on may 1 2001 (date)

by DENNIS HAMEL DISTRICT (KCC District Agent's Name)

Is ACO-1 filed? YES If not, is well log attached?

Producing Formation kansas city Depth to Top 3196-3214 Bottom 3214 T.D. 3230

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|------------|---------|------|------|-------|--------|------------|
| surface | 66 | 0-66 | | 8 5/8 | 66 | 0 |
| production | 0-3173 | | 3173 | 5 1/2 | 3173 | 0 |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.

Pipe was run to 2500 feet cement gel and hal were circulated to surface then 8 5/8 surface was tied onto and pumped down until pressured to 300 lbs then shut in about 320 sacks were used for plugging.

Name of Plugging Contractor allied cementing russel kansas license No.

Address RUSSELL KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: JOHNSON OIL


STATE OF kansas COUNTY OF phillips, sis.

(Employee of Operator) or (Operator) o above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above described well as filed the the same are true and correct, so help me God.

(Signature) *Waneta Gower*

(Address) 258 EAST HWY 36

SUBSCRIBED AND SWORN TO before me this 21st day of June, 2001



Waneta Fae Gower
Notary Public

My Commission Expires: 12-05-2003