

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

Form CP-1
September 2003
Form must be Typed
Form must be Signed
All blanks must be Filled

WELL PLUGGING APPLICATION

Please TYPE Form and File ONE Copy

API # 15- 189-21344 -00-01 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued.

Indicate original spud or completion date 6/17/89

Well Operator: Anadarko Petroleum Corporation KCC License #: 4549
(Owner/Company Name) (Operator's)

Address: 1201 Lake Robbins Drive City: The Woodlands

State: TX Zip Code: 77380 Contact Phone: 832 636-3128

Lease: Christopher "A" Well #: 1 Sec. 15 Twp. 33 R. 39 East West

NW - NW - SE - SE Spot Location/QQQQ County Stevens

1250 Feet from (in exact footage) North / South (from nearest outside section corner) Line of Section (not Lease Line)

1250 Feet from (in exact footage) East / West (from nearest outside section corner) Line of Section (not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well

SWD Docket # _____ ENHR Docket # _____ Other _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8" Set at: 1677' Cemented with: 350 Sacks

Production Casing Size: 4-1/2" Set at: 6547' Cemented with: 350 Sacks

List (ALL) Perforations and Bridgeplug Sets: CIBP @ 6470' Perfs 6075'-6079'; 6089'-6097'; 6100'-6108'

Elevation: 3220' (G.L. K.B.) T.D. 6550' PBDT 6470' Anhydrite Depth _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): _____

Spot cement plugs at 6025'-6108' and 2640'-3780'. Cut production casing off as deep as possible. Spot cement plug from 1620'-1730'; 450'-600'; and 4'-40'. Cut off at cap surface casing at 4'.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? Log was submitted with ACO-1

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

List Name of Company Representative authorized to be in charge of plugging operations:

Dawn Nease Phone: 620 544-6201

Address: P. O. Box 40 City/State Hugon, KS 67901

Plugging Contractor Sargent & Horton Plugging, Inc. KCC License # 31151
(Company Name) (Contractor's)

Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731 Phone: 405 854-6515

Proposed Date and Hour of Plugging (if known?): 7/16/04

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 7-15-04 Authorized Operator / Agent: Jerry N. Blossom
(Signature)

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Anadarko Petroleum Corporation
1201 Lake Robbins Drive
The Woodlands, TX 77380

July 16, 2004

Re: CHRISTOPHER A #1
API 15-189-21344-00-01
NWNWSESE 15-33S-39W, 1250 FSL 1250 FEL
STEVENS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888

Sincerely


David P. Williams
Production Supervisor