

RECEIVED
MAR 22 2004
KCC WICHITA

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15-159-03808-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 11-11-1958.

Well Operator: Bear Petroleum, Inc. (Owner / Company Name) KCC License #: 4419 (Operator's) 6/04
Address: P.O. Box 438 City: Haysville

State: KS Zip Code: 67060 Contact Phone: (316) 524-1225

Lease: Willhaus Well #: 2-6 Sec. 6 Twp. 21 S. R. 6 East West

C - SW - NW Spot Location / QQQQ County: Rice

~~1980~~ 1980 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

~~990~~ 990 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8 Set at: 165 Cemented with: 125 Sacks

Production Casing Size: 4 1/2 Set at: 3473 Cemented with: 100 Sacks

List (ALL) Perforations and Bridgeplug Sets: 3473-80' open hole

Elevation: 1690 (G.L. / K.B.) T.D.: 3480 PBTD: 3480 Anhydrite Depth: ? (Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Sand back to 3423', dump bail 4 sax cement, shoot pipe off, pull to 1050', 35 sax, 650', 35 sax, 215', circulate to surface, 60/40 poz 4% gel

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: _____

Bear Petroleum, Inc. Phone: (316) 524-1225

Address: P.O. Box 438 City / State: Haysville, KS 67060

Plugging Contractor: Mikes Testing & Salvage KCC License #: 31529 9/04
(Company Name) (Contractor's)

Address: P.O. Box 467, Chase, KS 67524-0467 Phone: (620) 938-2943

Proposed Date and Hour of Plugging (if known?): unknown

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 3-19-04 Authorized Operator / Agent: _____ (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

WELL LOG

Operator F. G. Holt
 Comm 11-10-58 Comp 11-23-58
 Shot _____ Qts. From _____ ft. To _____ ft.
 Acidized _____ Gal. _____
 Prod. Formation _____
 Initial Prod. _____
 Elevation _____

Lease Wilhaus Well No. 2
 Loc. Cen. SW NW Sec 6 Twp 21S Rge 6W
 County Rice State Kansas
 Contractor Red Drilling Company, Inc.

Casing Record

Size	Ft.	Pulled	Remarks
8 5/8"	162'	W/125 Sacks	2% C.C.
4 1/2"	3473'	W/100 Sacks	1/2% Floseal

RECEIVED
 MAR 22 2004
 KCC WICHITA

FIGURES INDICATE BOTTOM OF FORMATION

15	surface soil
75	sand & shale
168	lime & shale
195	shale & lime
240	shale
870	shale & shells - Red Bed Strks.
1035	shale & shells
1130	lime & shale strks
1505	lime & shale
1800	shale & lime
2000	shale & lime strks
2420	shale & lime
2630	lime & shale
2750	lime
2899	lime & shale
2950	shale & lime
3007	lime & shale
3041	lime
3090	lime & shale brks.
3334	lime
3474	lime & shale
3480	Chat

3473
 1690

 1783

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair John Wine, Commissioner Robert E. Krehbiel, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Bear Petroleum, Inc.
PO Box 438
Haysville, KS 67060

March 24, 2004

Re: WILHAUS #2-6
API 15-159-03808-00-00
E2SWNW 6-21S-6W, 1980 FNL 990 FWL
RICE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #2
130 S. Market, Room 2125
Wichita, KS 67202-3208
(316) 337-6231

Sincerely,


David P. Williams
Production Supervisor