

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM

File One Copy

RECEIVED
STATE CORPORATION COMMISSION

OCT 13 1976
10-13-76
CONSERVATION DIVISION
Wichita, Kansas

API Number 15 - 147 - 20221-000 (of this well)

Lease Owner Lowell Keesee

Address 797 3rd Street, Phillipsburg, Kansas 67661

Lease (Farm Name) EHM (Keesee) Well No. 1

Well Location C NW NE SW Sec. 23 Twp. 3S Rge. (E) 19 (W)

County Phillips County Total Depth 3225' Field Name

Oil Well Gas Well Input Well SWD Well Rotary D & A X

Well Log attached with this application as required Yes

Date and hour plugging is desired to begin 1:30 p.m. 10-6-76

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Joe Weber Address 409 Dorrance, Ellis, Kansas 67637

Plugging Contractor Abercrombie Drilling, Inc. License No.

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name Lowell Keesee

Address 797 3rd Street, Phillipsburg, Kansas 67661

and payment will be guaranteed by applicant or acting agent.

Signed: Jack L. Partridge
Applicant or Acting Agent

Date: October 11, 1976

15-147-20221-00-00

ABERCROMBIE DRILLING, INC.

801 UNION CENTER
WICHITA, KANSAS 67202

EHM #1 (Rig #10) - (Keesee)

C NW NE SW
Section 23-3S-19W
Phillips County, Kansas

OPERATOR: Lowell Keesee
CONTRACTOR: Abercrombie Drilling, Inc.

TEST: B/KC (Approx. 3450')

Lowell Keesee
797 3rd Street
Phillipsburg, Kansas 67661
(913) 543-5014

10-01-76 Moving in and rigging up.
10-02-76 Preparing to spud.
10-03-76 Drilling @1693'
Drilled 212' of 12 1/4 hole. Set 202' 8 5/8" surface at
212' K.B. Cemented with 150 sx cement 3% Cacl. cement
circulated, plug down 1:45 p.m. 10/02/76.
10-04-76 Drilling @ 2505'
10-05-76 Drilling @2970', Bit #3.
10-06-76 3225', Plugging
10-07-76 T.D. 3225', Set 1st plug at 900' with 70 sx.,
2nd plug at 185' with 20 sx., 3rd plug at 40' with
10 sx. Plug was down at 1:30 p.m. - 10-06-76.
State Plugger Leo Massey.

SAMPLE TOPS:

Anydrite 1538
B/Anydrite 1566

RECEIVED
STATE CORPORATION COMMISSION

OCT 13 1976

CONSERVATION DIVISION
Wichita, Kansas

10-13-76

15-147-20221-00-00

CONTRACTOR'S WELL LOG

OPERATOR: Lowell Keesee
CONTRACTOR: Abercrombie Drilling, Inc.
WELL NAME: EHM #1 (Keesee)
LOCATION: C NW NE SW, Section 23-3S-19W
Phillips County, Kansas
SPUD DATE: October 2, 1976
COMPLETION DATE: October 6, 1976

0	50	Clay
50	212	Shale
212	1072	Sand & Shale
1072	1270	Sand
1270	1538	Sand & Shale
1538	1566	Anhydrite
1566	2025	Shale
2025	2805	Shale & Lime
2805	3225	Lime & Shale
	3225	Rotary Total Depth

Drilled 212' of 12 $\frac{1}{4}$ " hole. Set 202' of 8 5/8" surface casing at 212' K.B. Cemented with 150 sx cement, 3% Ca. Cl. Cement circulated, plug was down at 1:45 p.m. 10-2-76.

T.D. 3225', Set 1st plug at 900' with 70 sx., 2nd plug at 185' with 20 sx., 3rd plug at 40' with 10 sx. Plug was down at 1:30 p.m. 10-6-76. State Plugger - Leo Massey.

SAMPLE TOPS:

Anhydrite 1538'
B/Anhydrite 1566'

RECEIVED
STATE CORPORATION COMMISSION

OCT 13 1976

10-13-76

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

CONSERVATION DIVISION
Wichita, Kansas

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby stat that the above and foregoing is a true and correct copy of the log of the EHM #1, C NW NE SW, Section 23-3S-19W, Phillips County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
Jack L. Partridge, Asst. Sec. Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 11th day of October, 1976.

Kathy S. Goertz
Kathy S. Goertz, Notary Public



COPY

State of Kansas



15-147-20 221-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

October 8, 1976

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Keesee
Description	C NW NE SW Sec. 23-3-19W
County	Phillips
Total Depth	3225
Plugging Contractor	Abercrombie Drilling


Lorell Keesee
797 3rd Street
Phillipsburg, Kansas 67661

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

Mr. Leo Massey, 109 West 15th, Hays, Kansas 67601
is hereby assigned to supervise the plugging of the above named well.