

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-147-20,209-00-00 (of this well) 6/87
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Petroleum Management, Inc. OPERATORS LICENSE NO. 5242

ADDRESS 400 N. Woodlawn, Suite 201, Wichita, KS 67208 PHONE # (316) 686-7287

LEASE (FARM) Bohl WELL NO. 1 WELL LOCATION C N $\frac{1}{2}$ N $\frac{1}{2}$ NW COUNTY Phillips

SEC. 13 TWP. 3 RGE. 19 (~~X~~) or (W) TOTAL DEPTH 3371' PLUG BACK TD 3299'

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 216' CEMENTED WITH 170 SACKS

CASING SIZE 4 1/2" SET AT 3342' CEMENTED WITH 150 SACKS

PERFORATED AT 3174-3238'

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Will pump 100 sx Econolite cement down
8 5/8" casing & 150 sx Econolite down 4 1/2" casing.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? N/A
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN April 2, 1987

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Wayne Fuzzell PHONE # (913) 434-2042

ADDRESS P. O. Box H, Plainville, KS 67663

PLUGGING CONTRACTOR Petroleum Management, Inc. LICENSE NO. 731

ADDRESS P. O. Box H, Plainville, KS 67663 PHONE # (913) 434-2042

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: W. Fuzzell
(Operator or Agent)

DATE: 3-18-87

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

3-23-87

6

15-147-20209-00-00
1 Mailed 2-19-76

Drillers Log

No. 1 Boh1

CASING RECORD:

8 5/8" @ 218'
w/170 sx cmt

COMPANY: Petroleum Management, Inc.

CONTRACTOR: Red Tiger Drilling Co.

COMMENCED: December 11, 1975

COMPLETED: December 18, 1975

DESCRIPTION: N $\frac{1}{2}$ N $\frac{1}{2}$ NW $\frac{1}{4}$
Sec. 13-3S-19W
Phillips County,
Kansas


TOTAL DEPTH: 3371'

ELEVATION: 1993' GL


<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale	0	195	
Shale	195	220	
Clay & Shale	220	650	
Sand	650	680	
Shale	680	870	
Shale	870	1075	
Sand	1075	1220	
Shale & Redbed	1220	1460	
Shale	1460	1507	
Anhydrite	1507	1529	
Shale & Shells	1529	1800	
Shale & Shells	1800	2093	
Shale & Lime	2093	2312	
Shale & Lime	2312	2443	
Shale & Lime	2443	2590	
Shale & Lime	2590	2752	
Lime & Shale	2752	2870	
Lime	2870	2980	
Lime	2980	3113	
Lime	3113	3200	
Lime	3200	3220	
Lime	3220	3250	
Lime	3250	3330	
Lime	3330	3371	
RTD		3371	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY


Jean Stocks

Subscribed and sworn to before me this 22nd day of December, 1975.


Notary Public

State of Kansas



15-147-20209-00-00

Mike Hayden
Michael Lennen
Margalee Wright
Keith R. Henley
Judith A. McConnell
Brian J. Moline

Governor
Chairman
Commissioner
Commissioner
Executive Secretary
General Counsel

State Corporation Commission
CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286
Ph. 316-263-3238

THIS NOTICE

JUN 23 '87

EXPIRES

March 23, 1987

WELL PLUGGING NOTICE

Bohl #1
C N/2 N/2 NW
Sec. 13-03S-19W
Phillips County

Petroleum Management, Inc.
400 N. Woodlawn, Ste. 201
Wichita, KS 67208

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

Jack McCord, Director

Please contact the district office to review your suggested method of plugging
DIST. #6 2501 E. 13th, Hays, KS 67601 (913) 628-1200
five days prior to plugging the well (KAR-82-3-113).