

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 03/92

RECEIVED  
STATE CORPORATION COMMISSION

MAY 08 1996

15-147-00903-00-01

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # Spud 4/7/52 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Petroleum Management, Inc. KCC LICENSE # 5242 <sup>6/96</sup>  
(owner/company name) (operator's)

ADDRESS 14201 East Central CITY Wichita

STATE KS ZIP CODE 67230 CONTACT PHONE # (316) 733-5600

LEASE Stuttgart Unit WELL# 303 SEC. 23 T. 3S R. 19 (East/West)

- NE - NW - NE SPOT LOCATION/QQQQ COUNTY Phillips

353 FEET (in exact footage) FROM S (N) (circle one) LINE OF SECTION (NOT Lease Line)

1502 FEET (in exact footage) FROM (E) W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# E-06,131

CONDUCTOR CASING SIZE N/A SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 264' CEMENTED WITH 225 SACKS

PRODUCTION CASING SIZE 5 1/2 SET AT 3322' CEMENTED WITH 150 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: DV 1459' 325 Perf 3173-82'; 3160-65'; 3133-40'; 3115-22'; 3082-89'

ELEVATION 1952 KB T.D. 3323 PBSD 3289 ANHYDRITE DEPTH 1445'  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Establish injection rate. Pump 10 sx cement with hulls followed by 300 sx 60-40 Poz plus 10% gel to surface.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? No

If not explain why? No ACO-1 in 1952

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Don Keener PHONE# (913) 434-2042

ADDRESS P. O. Box H City/State Plainville, KS 67663

PLUGGING CONTRACTOR Allied Cementing KCC LICENSE # N/A  
(company name) (contractor's)

ADDRESS P. O. Box 31, Russell, KS 67665 PHONE # (913) 483-2627

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) May 15, 1996.

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 5/7/96 AUTHORIZED OPERATOR/AGENT: Gary L. Reed  
(signature) Gary L. Reed

4)

STUTTGART UNIT #11

# Formation Record

*Stuttgart Ut.  
303*

Lease

**Hampler**

303

Well No.

8

| FROM | TO   | Formation         | REMARKS |
|------|------|-------------------|---------|
| 0    | 273  | Sand and Shale    |         |
| 273  | 500  | Shale             |         |
| 500  | 970  | Shale and Sand    |         |
| 970  | 1155 | Sand              |         |
| 1155 | 1175 | Redbed            |         |
| 1175 | 1445 | Shale and redbed  |         |
| 1445 | 1485 | Anhydrite - Shale |         |
| 1485 | 1815 | Shale and Shells  |         |
| 1815 | 2425 | Lime and Shale    |         |
| 2425 | 2865 | Shale             |         |
| 2865 | 3039 | Lime              |         |
| 3039 | 3084 | Lime and Shale    |         |
| 3084 | 3274 | Lime              |         |
| 3274 | 3323 | Lime and Shale    |         |

Tops: Howard 2843  
 Topeka 2870  
 Heebner 3041  
 Toronto 3064  
 LKC 3081  
 Base LKC 3303  
 Marmaton 3322

*Copy*

RECEIVED  
 STATE CORPORATION COMMISSION

MAY 08 1996



## Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner  
Judith McConnell, Executive Director David J. Heinemann, General Counsel

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

May 8, 1996

Petroleum Management Inc  
14201 E Central  
Wichita KS 67230

Stuttgart Unit #303  
API 15-N/A  
353 FNL 1502 FEL  
Sec. 23-03S-19W  
Phillips County

Dear Don Keener,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script that reads "David P. Williams".

David P. Williams  
Production Supervisor

District: #4  
2301 E 13th  
Hays KS 67601  
(913) 628-1200