

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
Wichita, Kansas 67217

Rev. 3-15-72
FORM CP-1

RECEIVED
STATE CORPORATION COMMISSION

AUG 14 1974

CONSERVATION DIVISION
Wichita, Kansas

8-14-74

WELL PLUGGING APPLICATION FORM
File One Copy

15-147-00900-00-00
01

RECEIVED
STATE CORPORATION COMMISSION
AUG 6 1974
CONSERVATION DIVISION
Wichita, Kansas
8-6-74

Lease Owner PETROLEUM MANAGEMENT, INC.
Address P. O. BOX 1325, GREAT BEND, KANSAS 67530
Lease (Farm Name) Vogel Well No. 1
Well Location NE NE SE Sec. 14 Twp. 3S Rge. (E) (W) 19
County PHILLIPS Total Depth 3550' Field Name Stuttgart LKC
Oil Well Gas Well Input Well XX SWD Well Rotary D & A
Well Log filed with application as required Attached
Date and hour plugging is desired to begin Unknown

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

DONALD H. KEENER

Address 2305 WALNUT, HAYS, KANSAS 67601

Plugging Contractor PETROLEUM MANAGEMENT, INC. License No. 731

Address 499 NO. WOODLAWN, SUITE+201, WICHITA, KANSAS 67208

Invoice covering assessment for plugging this well should be sent to:

Name PETROLEUM MANAGEMENT, INC.

Address P. O. BOX 1325, GREAT BEND, KANSAS 67530

and payment will be guaranteed by applicant or acting agent.

Signed: 
Applicant or Acting Agent

Date: AUGUST 5, 1974

Phillips Pet. Co.
 NE 1/4 SE Sec. 14-3-19W
 330' EL. & 2310' SL
 T.D. 3550, PB 3298

15-147-00900-00-00
 01
Formation Record

Phillips Pet. Co.
 Phillips County
 Comm. 1-16-51
 Comp. 4-1-51
 8" 1505
 5" 3341

I.P. BHP 710 BOPD
 Lease V0591

Well No. 2

FROM	TO	Formation	REMARKS
0	55	Surface Clay	Elevation: Ord. 1901°
55	100	Sandy Shale	Derrick Floor 1903° R. K. B. 1905°
100	232	Shale	Note: P.B. 3298, Log 3266-76, Rec. 2 Gal. water, trace oil, 500 gallons, swb 5 BW/8 hole swabbed dry.
232	247	Sand & Shale	Set Lane-Well Plug 3210, Perf. 36 holes 3190-99, Rec. 2 1/2 BW & SSO 500 gallons, swb 1 BWPB, Swb. 16 Gallons salt water & 5 Gallons oil in 5 hours.
247	535	Shale & Shells	Set Lane Well Plug 3185, Perf. 40 Shots 3116-56 bailed 7 GOPH for 8 hours 500 gallons, swb. 70 BO/2hours, Swab 35.67 BOPD for four hours.
535	675	Sand & Shale	LWP 3135 Perf. 40 Shots 3114 to 3124, Swab 9 BO no water per hour for 10 hours 2000 gals., Swb. 43 BO & 51 BO for next two hours.
675	815	Shale & Shells	Drilled out plug to 3176 and Well is producing from 3116 to 3156 & 3114 to 3124
815	980	Shale & Sand	Top Anhydrite 1460°
980	1190	Sand	Base Anhydrite 1498°
1190	1220	Shale & Shells	
1220	1360	Redbed & Shells	
1360	1460	Redbed & Shale	
1460	1498	Anhydrite	
1498	1815	Shale	
1815	3101	Line & Shale	Top: Howard 2872°; Topain 2887° Bill Zone 2900°; Inctney 2972° Toronto 2996°; L.R.C. 3114°
3101	3346	Coring	
3346	3365	Line & Shale	Top Hamaten 3342°
3365	3550	Line	Top: Conglomerate 3401°; Arbuckle 3550° 3498

PB 3298

RECEIVED
 STATE CORPORATION COMMISSION

AUG 14 1974

CONSERVATION DIVISION
 Wichita, Kansas

8-14-74



15-147-00900-00-86

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027

3830 S. Meridian

WICHITA, KANSAS 67217

August 14, 1974

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Vogel
Description	NE NE SE 14-3-19W
County	Phillips
Total Depth	3550'
Plugging Contractor	Petroleum Management, Inc.


Petroleum Management, Inc.
P. O. Box 1325
Great Bend, Kansas 67530

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

Mr. Leo Massey, P. O. Box 582, Hays, Kansas 67601
is hereby assigned to supervise the plugging of the above named well.