

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-191-10086-00-01

Spot: NWSESE

Sec/Twnshp/Rge: 32-31S-1W

1320 feet from S Section Line,

990 feet from E Section Line

Lease Name: WELLINGTON

Well #: 70-I

County: SUMNER

Total Vertical Depth: 3714 feet

Operator License No.: 5147

CIBP Size: feet: 3647

Op Name: BEREDCO, INC.

CIBP Size: feet: 3665

Address: PO BOX 20380

PROD Size: 7 feet: 3676 350'

WICHITA, KS 67208

SURF Size: 12.5 feet: 335 250'

\$120<sup>71</sup>

Well Type: EOR

UIC Docket No: E03396.8

Date/Time to Plug: 07/08/2004 2:50 PM

Plug Co. License No.: 30437

Plug Co. Name: UNITED CEMENTING AND ACID CO., INC.

Proposal Rcvd. from: JASON BRUNS

Company: BEREDCO, INC.

Phone: (620) 886-2080

Proposed  
Plugging  
Method:

Sand bottom to 3620' and 10 sxs; Squeeze hole at 80' - 110'; Ran tubing to 385'; pump 70 sxs; squeezed 50 sxs.

RECEIVED  
KCC DISTRICT #2

JUL 20 2004

Plugging Proposal Received By: STEVE VANGIESON

WitnessType: NONE

WICHITA, KS

Date/Time Plugging Completed: 07/08/2004 2:50 PM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:

The perforations were sanded back to 3620' and capped with 10 sacks of cement. Ran tubing to 385' and filled 7" with 70 sacks of cement. Squeezed hole in casing 80' - 110' with 50 sacks of cement. S.I. 200#.

60/40 posmix with 4% gel.

Top	Bot	Thru	Comments
3676	3714		


RECEIVED  
JUL 30 2004  
KCC WICHITA

Remarks: UNITED CEMENT #6132

Plugged through: TBG

District: 02

Signed

  
INVOICED (TECHNICIAN)

DATE

7-30-04

WV. NO.

2005060253