

4-070172

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-147-20,298 ⁻⁰⁰⁰⁰
100 E. of
N2 SE NE /4 SEC. 23, 03 S, 19 W
3630 feet from S section line
550 feet from E section line

Operator license# 5242

Lease: EHM Stuttgart Well # 2

Operator: Petroleum Mangement, Inc. 5/12

County: Phillips 108.55

Address: 14201 East Central
Wichita, Kansas 67230

Well total depth 3340 feet
Conductor Pipe: 0 inch @ 0 sxs.
Surface pipe 9 5/8 Inch @ 211 feet
W/125 sxs.

ABAND. oil well , Gas well , Input well , SWD. , D&A

Plugging contractor: Petroleum Management, Inc. License# 5242

Address: 14201 East Central - Wichita, Kansas 67230

Company to plug at: Hour: 8:30 A.M. Day: 12 Month: May Year: 2000

Plugging proposal received from: Larry Wallert

Company: Petroleum Management, Inc. Phone: 785-483-5802

Were: PBTD 3310'. Perforations 3153' - 3182'.
Squeeze 930' with 150 sxs.

Plugging Proposal Received by: Larry Wallert

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 10:00 A.M. Day: 12, Month: May, Year: 2000

Actual plugging report: Pfeifer Well Service ran tubing to 2007'. Allied pumped 60 sxs
60/40 pozmix - 10% gel with 300# hulls. Pulled tubing to 917'. Allied pumped 80 sxs with
200# hulls. PTOH. Squeezed 30 sxs. Max. P.S.I. 400#. S.I.P. 200#.

Hooked up to backside 4 1/2" - pumped 30 sxs with Max. P.S.I. 200#. S.I.P. 100#.

RECEIVED
STATE CORPORATION COMMISSION

MAY 18 2000

Remarks: _____
CONSERVATION DIVISION
Wichita, Kansas

Condition of casing (in hole): GOOD BAD Anhy. plug: YES NO

Bottom plug (in place): YES , CALC , NO Dakota plug: YES , NO

Plugged through TUBING , CASING . Elevation: 1965 GL

I did [] / did not [] observe the plugging.

Richard Williams
(agent)

Form CP-2/3

INVOICE NO. 40
DATE 5/19/00
WEL. NO. 61755

(R)