

4-070175

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-147-20264-0000
200'E.of
SW NE NE /4 SEC. 23, 03 S, 19 W
4290 feet from S section line
790 feet from E section line

Operator license# 5242

Lease: Stuttgart Well # 306

Operator: Petroleum Mangement, Inc.

County: Phillips 108.06

Address: 14201 East Central
Wichita, Kansas 67230

Well total depth 3325 feet
Conductor Pipe: 0 inch @ 0 sxs.
Surface pipe 9 5/8 Inch @ 214 feet
W/135 sxs.

ABAND. oil well X, Gas well , Input well , SWD. , D&A

Plugging contractor: Petroleum Management, Inc. License# 5242

Address: 14201 East Central - Wichita, Kansas 67230

Company to plug at: Hour: P.M. Day: 23 Month: May Year: 2000

Plugging proposal received from: Larry Wallert

Company: Petroleum Management, Inc. Phone: 785-483-5802

Were: 5 1/2" casing set at 3325' w/200 sxs. PBTB 3205'.

Perfs at 3117' - 3185'.

Ordered out 350 sxs 60/40 pozmix - 10% gel with 500# hulls.

RECEIVED
STATE CORPORATION COMMISSION

JUN 1 2000

Plugging Proposal Received by: Rich Williams

CONSERVATION DIVISION
Wichita, Kansas

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 2:50 P.M. Day: 23, Month: May, Year: 2000

Actual plugging report: Allied pumped 280 sxs 60/40 pozmix with 500# hulls - cement
circulated out backside. Shut in 2" valve on backside. Squeezed 25 sxs with 100# hulls.
Max. P.S.I. 400#. S.I.P. 300#.

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO

Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO

Plugged through TUBING , CASING X. Elevation: 1949 GL

I did [X] / did not [] observe the plugging.

Richard Williams
(agent)

Form CP-2/3

INVOICED
DATE 6/7/00
INV. NO. 61827

(R)