

4-070174

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-147-20179-0000  
100' W. of  
S2 SE NE /4 SEC. 23, 03 S, 19 W  
2970 feet from S section line  
760 feet from E section line

Operator license# 5242

Lease: EHM Stuttgart Well # 1

Operator: Petroleum Mangement, Inc.

County: Phillips

Address: 14201 East Central  
Wichita, Kansas 67230

Well total depth 3343 feet  
Conductor Pipe: 0 inch @ 0 sxs.  
Surface pipe 9 5/8 Inch @ 207 feet  
W/150 sxs.

ABAND. oil well X, Gas well     , Input well     , SWD.     , D&A     

Plugging contractor: Petroleum Management, Inc. License# 5242

Address: 14201 East Central - Wichita, Kansas 67230

Company to plug at: Hour: 3:00 P.M. Day: 23 Month: May Year: 2000

Plugging proposal received from: Larry Wallert

Company: Petroleum Management, Inc. Phone: 785-483-5802

Were: 4 1/2" casing set at 3341' w/150 sxs. PBTD 3275'.

Perfs at 3172' - 3236'.

Holes in casing 800' - 2200'.

Ordered out 350 sxs 60/40 pozmix - 10% gel with 600# hulls.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 1 2000

CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by: Rich Williams

Plugging operations attended by agent? All  , Part  , None

Completed: Hour: 5:00 P.M. Day: 23 , Month: May , Year: 2000

Actual plugging report: Ran 2 3/8" tubing to 2800'. Allied pumped 100 sxs 60/40 pozmix - 10% gel with 300# hulls. Pulled to 1450'. Allied pumped 120 sxs with 200# hulls - circulated cement. PTOH. Allied squeezed 40 sxs. Max. P.S.I. 500#. S.I.P. 300#. Hooked up to backside - pumped 50 sxs with 100# hulls. Max. P.S.I. 400#. S.I.P. 300#.

Remarks: Emergency plug orders given while rig over hole.

Condition of casing(in hole): GOOD  BAD  Anhy.plug: YES  NO

Bottom plug(in place): YES  , CALC  , NO  Dakota plug: YES  , NO

Plugged through TUBING  , CASING  . Elevation: 1997 GL

I did  / did not  observe the plugging.

Richard Williams  
(agent)

Form CP-2/3

INVOICED

DATE 6/7/00

INV. NO. 61827

(R)