

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-23142-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 26-34S-11E
1400 feet from S Section Line, 5050 feet from E Section Line
Lease Name: BOWMAN Well #: 20
County: CHAUTAUQUA Total Vertical Depth: 1200 feet

Operator License No.: 32026
Op Name: HESSERT LOC INC
Address: 103 DORA AVE.
SEDAN, KS 67361

PROD Size: 4.5 feet: 1200
SURF Size: 7 feet: 0

80
#39

Well Type: OG UIC Docket No: Date/Time to Plug: 06/21/2004 8:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S INC.
Proposal Rcvd. from: JOHN ELMORE Company: ELMORE'S INC. Phone: (620) 249-2519

Proposed TO PUMP CEMENT AND GEL FOR BOTTOM & TOP PLUGS.
Plugging
Method:

Plugging Proposal Received By: RON ROWE WitnessType: NONE
Date/Time Plugging Completed: 06/21/2004 5:00 PM KCC Agent: RON ROWE

Actual Plugging Report:

BULLHEAD PUMPED 15 SACKS CEMENT & GEL DOWN 4.5" CASING FOR BOTTOM PLUG @ 1200' & GEL SPACER, THEN PRESSURED TO 600#. PERFORATED 4.5" @ 350'. RAN 1" SPOOL HOSE IN 4.5" TO 350' & PUMPED/CIRCULATED CEMENT TO SURFACE, INSIDE & OUTSIDE 4.5". PULLED SPOOL HOSE & TOPPED-OFF WELL. USED TOTAL OF 102 SACKS CEMENT & 2 SACKS GEL.

Perfs:

RECEIVED
JUL 30 2004
KCC WICHITA


RECEIVED
KCC DISTRICT #3
JUL 20 2004 RR
CHANUTE, KS

Remarks:

Plugged through: CSG

District: 03

Signed


(TECHNICIAN)

INVOICED
DATE 7-30-04
FILE NO. 2005060255