

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-049-21689-00-00
Spot: NESWSWSE Sec/Twnshp/Rge: 15-30S-10E
495 feet from S Section Line, 2310 feet from E Section Line
Lease Name: BAUDER C Well #: 1
County: ELK Total Vertical Depth: 2110 feet

Operator License No.: 3591
Op Name: TRIBOULET, ED DBA C & E OIL CO.
Address: RR1, BOX 1B2
MOLINE, KS 67353

PROD Size: 5.5 feet: 2110
SURF Size: 8.625 feet: 169

\$6858

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/01/2004 8:00 AM
Plug Co. License No.: 3591 Plug Co. Name: TRIBOULET, ED DBA C & E OIL CO.
Proposal Rcvd. from: ED TRIBOULET Company: TRIBOULET, ED DBA C & E OIL C Phone: (620) 647-3601

Proposed Plugging Method: TO SAND BACK, THEN PUMP CEMENT FOR BOTTOM, MIDDLE, & TOP PLUGS.

Plugging Proposal Received By: RON ROWE WitnessType: NONE
Date/Time Plugging Completed: 06/01/2004 5:00 PM KCC Agent: RON ROWE

Actual Plugging Report:

DUMP-BAILED, SANDED BACK TO 2060'. RAN 2" TUBING WORK-STRING INSIDE 5.5" CASING TO 2060' & PUMPED 10 SACKS CEMENT FOR BOTTOM PLUG. PULLED 2" TO 1100' & PUMPED 5 SACKS CEMENT. PULLED 2" TO 450' & PUMPED/CIRCULATED CEMENT TO SURFACE. PULLED 2" & TOPPED-OFF WELL. USED TOTAL OF 60 SACKS CEMENT.

Perfs:

Top	Bot	Thru	Comments
2054	2062		

RECEIVED
JUL 30 2004
KCC WICHITA

RECEIVED
KCC DISTRICT #3
JUL 26 2004 *RR*
CHANUTE, KS

Remarks:

Plugged through: TBG

District: 03

Signed

[Signature]
(TECHNICIAN)

INVOICED

DATE

7-30-04

INV. NO.

2005060261