

8-12 4-070105

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-147-20,060 00-00

SE SW SE /4 SEC. 26, 03 S, 19 W  
330 feet from S section line  
1650 feet from E section line

Operator license# 6484

Lease: Veeh Well # 1

Operator: Anderson Energy

County: Phillips 111,87

Address: 200 East First - #414  
Wichita, Kansas 67202

Well total depth 3442 feet  
Conductor Pipe: 0 inch @ 0 sxs.  
Surface pipe 7 Inch @ 219 feet  
W/100 sxs.

ABAND. oil well , Gas well , Input well , SWD. , D&A

Plugging contractor: Anderson Energy License# 6484

Address: 200 East First - #414 - Wichita, Kansas 67202

Company to plug at: Hour: 10:00 A.M. Day: 12 Month: August Year: 1998

Plugging proposal received from: Wally Wahlmeier

Company: Anderson Energy, Inc. Phone: 785-625-2725

Were: 4 1/2" set at 3441' w/100 sxs.  
Perfs at 3246' - 3284'. Anhy. 1558'.  
Ordered 250 sxs 60/40 pozmix - 10% gel with 500# hulls.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All , Part , None

Completed: Hour: 1:15 P.M. Day: 12, Month: August, Year: 1998

Actual plugging report: Ran 2 3/8" tubing to 3030'. Allied pumped 100 sxs 60/40 pozmix - 10% gel with 300# hulls. Pulled tubing to 1530' - pumped 85 sxs cement with 200# hulls. Cement circulated. PTOH. Topped off with 15 sxs. Hole stayed full. Hooked up to backside and pumped 50 sxs 60/40 pozmix - 10% gel. Max. P.S.I. 200#. S.I.P. 100#.

Remarks:

Condition of casing(in hole): GOOD  BAD  Anhy.plug: YES  NO

Bottom plug(in place): YES , CALC , NO  Dakota plug: YES , NO

Plugged through TUBING , CASING  Elevation: 2054 GL

I did  / did not  observe the plugging.

Richard Williams  
(agent)

Form CP-2/3

**INVOICED**

DATE 8-20-98

INV. NO. 51181

8-26-1998