

4-090522

9-14

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-147-20,559 ⁰⁰⁻⁰⁰

W2 W2 NE /4 SEC. 26, 03 S, 19 W
1320 feet from S section line
2310 feet from W section line

Operator license# 6484

Lease Veeh well # 5

Operator: Anderson Energy, Inc.

County Phillips

Address: 200 E. First
Suite #414
Wichita, Kansas 67202

Well total depth 3370 feet ^{109.52}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 223 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: White & Ellis Drilling, Inc. License# 5420

Address: Wichita, Kansas 67202

Company to plug at: Hour: P.M. Day: 13 Month: September Year: 94

Plugging proposal received from: Judy

Company: White & Ellis Drilling, Inc. Phone:

Were: Order 170 sxs. 60/40 posmix - 6% gel and 1 sack celloflake.
Spot all plugs through drill pipe with heavy mud between all plugs.

Plugging Proposal Received by: Ed Schumacher
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 5:15P.M., Day: 14, Month: September, Year: 94

Actual plugging report:

1st. plug at 1570' w/25 sxs.

2nd. plug at 935' w/80 sxs.

3rd. plug at 275' w/40 sxs.

4th. plug at 40' w/10 sxs.

15 sxs. in rathole.

Arbuckle - No.

RECEIVED
STATE CORPORATION COMMISSION

SEP 20 1994

CONSERVATION DIVISION
WICHITA, KANSAS

92094

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD Anhy. plug: YES 1550 NO

Bottom plug(in place): YES , CALC , NO ✓ Dakota plug: YES ✓, NO

Plugged through TUBING , CASING . Elevation: 2037 GL

I did [X] did not [] observe the plugging.

Ed Schumacher

DATE 9-28-94

(agent)

Form CP-2/3

INV. NO. H1290

HO.