

4-032188

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

12-10

API Number: 15-147-20,272 ~00-00

SE NE SW /4 SEC. 26, 03, 19 W
1550 feet from S section line
3040 feet from E section line

Operator license# 5352

Lease: Vogel Well # B-1

Operator: Baird Oil Company, Inc.

County: Phillips 111.15

Address: P.O. Box 428
Logan, Kansas 67646

Well total depth 3420 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 248 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 10 Month: December Year: 1996

Plugging proposal received from: Jim Baird

Company: Baird Oil Company, Inc. Phone:

Were: Order 150 sxs 60/40 pozmix - 10% gel - 300# hulls - 10 sxs gel.

12-19-96

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 1:00 P.M., Day: 10, Month: December, Year: 1996

Actual plugging report: 8 5/8" set at 248' w/165 sxs. 4 1/2" set at 3419' with 235 sxs. P.B.T.D. at 3398. Prod. Perfs 3212' - 3234'. Critical area control shots at 1540' and 980'. Squeezed 4 1/2" w/25 sxs cement followed by 10 sxs gel with 200# hulls mixed in, followed by 100 sxs cement blend to Max. P.S.I. 500#. Held. Squeezed backside with 25 sxs cement blend with 100# hulls mixed into Max. P.S.I. 400#. Held. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: GL

I did [X] / did not [] observe the plugging.

Carl Goodrow (agent)

Form CP-2/3

INVOICED
DATE DEC 31 1996
INV. NO. 47195