

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-01375-00-01
Spot: SENENW Sec/Twnshp/Rge: 14-9S-21W
4290 feet from S Section Line, 2970 feet from E Section Line
Lease Name: HINKHOUSE OWWO Well #: 2
County: GRAHAM Total Vertical Depth: 3701 feet

Operator License No.: 5147
Op Name: BEREDCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

PROD Size: 5.5 feet: 3691
SURF Size: 8.625 feet: 215 w/135 sxs cmt

120²⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/26/2004 9:30 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: DENNIS KIRMER Company: BEREDCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered 265 sxs 60/40 pozmix - 10% gel - 500# hulls - 9 sxs gel.
1953 -squeezed at 1131' - 1160. 1995 - squeezed at 1944' -2742' w/400 sxs.
CIBP 3606' - 3656'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/26/2004 12:40 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with tubing 3555'.
Pumped 50 sxs 60/40 pozmix with 200# hulls mixed in.
Pulled tubing to 2800' - pumped 9 sxs gel.
Pulled tubing to 2000' - pumped 70 sxs cement with 100# hulls mixed in.
Pulled tubing to 1000' - pumped 50 sxs cement with 100# hulls mixed in.
Cement circulated into pit.
Pulled tubing and tied onto 5 1/2" casing with a swedge - pumped 50 sxs cement.
Max. P.S.I. 250#. S.I.P. 100#.
Tied onto 8 5/8" annulus - pumped 45 sxs 60/40 pozmix.
Max. P.S.I. 200#. S.I.P. 50#.

RECEIVED
JUL 30 2004
KCC WICHITA

Perfs:


Top	Bot	Thru	Comments
3490	3493		
3478	3481		
3472	3474		
3454	3456		
3399	3493		

Remarks: ALLIED CEMENTING COMPANY-TICKET #14928.

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

INVOICED


DATE 7-30-04
INV. NO. 2005060253

Form CP-2/3

JUL 28 2004

12-235 Map No. _____ OWWO
 OPER. CRA, INC.

Great Bend, Kansas
 WELL #2 HINKHOUSE
 CONTR _____



S-T-R 14-9S-21W
 SPOT SE NE NW
 CO GRAHAM, Ks
 ELEV 2224 OKB

FIELD Morel (LKC & Arb Oil)
 I.P. P 100 BO / 229 wtr/24 hrs, (54" stroke x
 16 1/2 SPM) 1 1/2" Pump Lans 3399-3493

(Old Spls:)
 Hb 3356 -1132
 Tor 3382 -1158
 Lans 3399 -1175
 Cg 3671 -1447
 Sp 3673 -1449
 Arb 3691 -1467
 RTD 3695 -1471
 DDTD 3701 -1477

OLD INFO: (Was Bridgeport #2 Hinkhouse) (Spd 8-8-44
 8" @215' w/135 Sx.)
 No DST's, No Cores, RTD 3695, 5 1/2" @3691', CO 3695 TD
 FU 2100' oil/7 hrs, § 85 BO/3 hrs, DD 3698, § 134 BO/
 3 hrs, (1200' OB) DD 3701 TD, FU 2840' Oil/12 hrs, §
 31 BOPH/12 hrs, (1400' OB) POP, Deptho 4591 BOPD, Gr
 28.4 deg, Arb OH 3691-3701 - Comp 8-30-44
NEW INFO: (12-16-65)
 PB 3606, 9/3490-93, 6/3479-81, 6/3472-74, 6/3454-56,
 6/3399-3402 (Lans) 5000A, All perms (3399-3493) 1500
 MA (3399-3402) § 1d, FU 425 oil / 425 wtr/12 hrs, POP
 P 137 BO / 39 BW/24 hrs, State Pot: P 100 BO / 229 wtr/
 24 hrs, (54" stroke x 16 1/2 SPM) 1 1/2" Pump - FIRST REPORTED
 & COMPLETED 12-16-65

Data Inc

IMADICEP