

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-02834-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 5-9S-24W
4950 feet from S Section Line, 4950 feet from E Section Line
Lease Name: HOLLEY UNIT Well #: 14-1
County: GRAHAM Total Vertical Depth: 3974 feet

Operator License No.: 30420
Op Name: INNONE, VINCENT D/B/A V.J.I. NATUR
Address: 30-38 48TH STREET
ASTORIA, NY 11103

PROD Size: 5.5 feet: 3962 75 SX CMT
SURF Size: 8.625 feet: 166 115 SX CMT

\$129¹⁴

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/28/2004 12:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JASON DINGES Company: V.J.I. NATURAL RESOURCES, INC. Phone: (785) 625-8360

Proposed Plugging Method: Ordered out 400 sxs 60/40 pozmix - 10% gel - 700# hulls.
Cleaned out bridge at 1640' (iron sulfide) to 1700'.
Circulated clean to 2100'. Casing leaks.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/28/2004 1:45 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2100'.
Allied pumped 250 sxs cement with 400# hulls.
Cement circulated.
PTOH.
Squeezed with 85 sxs cement with 100# hulls.
Max. P.S.I. 500#. S.I.P. 200#.
Hooked up to backside and pumped 75 sxs cement with 200# hulls.
Max. P.S.I. 100#.

RECEIVED
JUL 30 2004
KCC WICHITA

Perfs:

Top	Bot	Thru	Comments
3795	3962		

Remarks: LEASE PREVIOUSLY KNOWN AS WAITE #1. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

JUL 29 2004

INVOICED
DATE 7-30-04
INV. NO. 2005060256

EMPIRE DRILLING CO., ETAL

#1 WAITE

5-9-24W
NW NW NW

Contr. EMPIRE DRLG

GRAHAM

County

E 2474RB

Comm. 1-5-57

Comp. 2-15-57

IP 265 BOPD/LANS

PHY POT

Tops	Depth	Datum
ANH	2166	+308
HEEB	3755	-1281
TOR	3778	-1304
KC	3795	-1321
TD	3975	-1501

Casing

8" 166

5" 3962

DST 3830-45/1 HR, 10' 0, 35' H OCM, BHP 1260#

DST 3850-65/1 1/2 HRS, 300' G, 30' 0, 20' MDY WTR, BHP 1190#

DST 3912-35/1 HR, 610' G, 50' 0, 60' SL SLTY WTRY 0 & GCM, BHP 1090#

DST 3935-55/70", 615' G, 70' 0, 35' 0 & GCM, BHP 480#

HOLLEY

SWB 6 1/2 BOPH, NATL: FU
1000' 0/3 HRS: ACID 3000
SWB 50 BOPH/5 HRS

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS