

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-02727-00-00  
Spot: S2NWNWSW Sec/Twnshp/Rge: 31-8S-24W  
2310 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: HOLLEY Well #: 6-2  
County: GRAHAM Total Vertical Depth: 4002 feet

Operator License No.: 30420  
Op Name: INNONE, VINCENT D/B/A V.J.I. NATUR  
Address: 30-38 48TH STREET  
ASTORIA, NY 11103

PROD Size: 7 feet: 4001 100 SX CMT  
SURF Size: 10.75 feet: 318 200 SX CMT

\$ 130<sup>07</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/15/2004 10:00 AM

Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: JASON DINGES Company: V.J.I. NATURAL RESOURCES, INC. Phone: (785) 625-8360

Proposed Plugging Method: Ordered out 450 sxs 60/40 pozmix - 10% gel - 600# hulls.  
Cleaned out bridges at 600'.  
Ran tubing to 2100' - circulated clean.  
D.V. at 2160' with Black Magic.

Plugging Proposal Received By: HERB DEINES  
Date/Time Plugging Completed: 07/15/2004 12:00 PM

Witness Type: COMPLETE (100%)  
KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2100'.  
Allied pumped 310 sxs 60/40 pozmix - 10% gel with 600# hulls.  
Pulled tubing to 1000'. Allied pumped 100 sxs cement - circulated.  
PTOH. Allied topped off with 40 sxs cement - dropping - will top off and check backside.  
07-23-2004 - Topped off 7" with 25 sxs cement - casing full.  
Allied pumped 50 sxs 60/40 pozmix down backside.  
Max. P.S.I. 200#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3776	4001		

RECEIVED  
JUL 30 2004  
KCC WICHITA

Remarks: LEASE PREVIOUSLY KNOWN AS W.L.BELL #2. EMERGENCY PLUG ORDERS GIVEN WHILE RIG OVER HOLE. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams  
(TECHNICIAN)

AD.

JUL 29 2004

INVOICED  
DATE 7-30-04  
INV. NO. 2005060256

Aka Holly 6-2

TEXAS COMPANY

#2 W L BELL

31-8-24W  
NW 1/4 SW

Contract ... WELLS DRLG

GRAHAM ... County

E. 2/1/4 ... Corner


1-10-55 comp. 12-16-55 IP 97 BOPD

Tops	Depth	Datum
HEEB	3756	-1292
LANS	3772	-1328
TD	4002	-1558

Casing

8" 318  
7" 4001  
TST 30 BO & 12 BW/2 HR  
PACKER 3918: SQZ: PERF 2 1/4  
3948-54: TST 35 GW/1ST HR  
ACID 2000: PB: SWB 28 BO &  
5 1/2 BW: PMP 29 BO, TR WTR/  
8 HR:

HOLLY WEST



360' SOUTH  
330' EAST OF NW COR  
SW/4

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS