

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-22008-00-00  
Spot: SWSWSW Sec/Twnshp/Rge: 12-14S-15W  
330 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: MILLS Well #: 2  
County: RUSSELL Total Vertical Depth: 3339 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 4514 COLE AVE., STE 740, LB 30  
DALLAS, TX 75205

PROD Size: 4.5 feet: 3339 w/175 sxs cmt  
SURF Size: 8.625 feet: 530 w/275 sxs cmt

\$ 108<sup>52</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/27/2004 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL OPERATIONS, INC. Phone: (785) 483-2169

Proposed  
Plugging  
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/27/2004 10:30 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Tied onto casing and pumped 200 sxs 60/40 pozmix - 10% gel cement with 400# hulls.  
Max. P.S.I. 500#. S.I.P. 100#.  
Pressured backside to 500# P.S.I.

Perfs:

Top	Bot	Thru	Comments
3274	3276		
3215	3219		
3111	3114		
3100	3103		
3055	3058		

RECEIVED  
JUL 30 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed \_\_\_\_\_

Case Morris

(TECHNICIAN)

INVOICED

DATE

7-30-04

INV. NO.

2005060259

Form CP-2/3

JUL 27 2004

DRISCOLL LEASE OPERATIONS, INC.  
726 MAIN

#2 MILLS

12-14-15W  
SW SW SW


RUSSELL, KS 67665

CONTR REVLIN DRILLING, INC.

CTY RUSSELL

GEOL ROY KRUEGER

FIELD GORHAM



ELV 1863 KB SPD 10/2/82 CARD ISSUED 1/20/83 P 25 BOPD, TR WTR

ARB 3289-3291

API 15-167-22,008

LOG	Tops .....	Depth/Datum
ANH	.....	893+ 970
TOP	.....	2750- 887
HEEB	.....	2974-1111
TOR	.....	2993-1130
LKC	.....	3029-1166
ARB	.....	3275-1412
RTD	.....	3339-1476

8 5/8 " 530/275SX; 4 1/2 " 3339/175SX  
NO DSTS  
MICT - CO, PF (ARB) 3289-91, W / 4 SPF, AC 150G, SWB LD,  
GSO, POP, P 25 BOPD, TR WTR, 10/28/82

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS