

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-19002-00-01
Spot: CNWSW Sec/Twnshp/Rge: 1-3S-19W
660 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: SOUTH KAISER Well Number: 1
County: PHILLIPS Total Vertical Depth: 3230 feet

Operator License No.: 3077
Op Name: JOHNSON OIL
Address: 258 HWY 36
PHILLIPSBURG, KS 67661

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 66 150 SX CMT
Production: Size 5.5 feet: 3173 200 SX CMT
Liner: Size feet:

\$104.98

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/08/2001 8:00 AM
Plug Co. License No.: 3077 Plug Co. Name: JOHNSON OIL
Proposal Rcvd. from: KEVIN JOHNSON Company: JOHNSON OIL Phone: (785) 543-6171

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/08/2001 1:30 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

RIH with tubing 1835'.
Spotted 180 sxs cement with 400# hulls to circulate with cement at surface.
P.O.O.H. with tubing and squeezed 5 1/2" casing with 100 additional sxs cement.
Max. P.S.I. 400#. S.I.P. 300#.
RU Cementers to 8 5/8" S.P.
Squeezed 35 sxs cement with 100# hulls.
Max. P.S.I. 400#. S.I.P. 300#.

INVOICED
DATE 6-14-01
INV. NO. 2001061931

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 13 2001
CONSERVATION DIVISION

Remarks: LEASE ALSO KNOWN AS KATZ #1. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

100

Signed


Dennis L. Hamel

(TECHNICIAN)

MAY 30 2001

JOHNSON OIL
 RT. #3
 PHILLIPSBURG, KS 67661
 CONTR COMPANY TOOLS
 GEOL _____
 ELV 2020 GL SPD 12/10/83
 #1 KAISER "OWWO"
 CTY PHILLIPS
 FIELD DAYTON
 CARD ISSUED 7/5/84
 IP P 6 BOPD
 LKC 3196-3214 OA

1-3-19W
 C NW SW



SMP	Tops	Depth/Datum
ANH	1508+ 512
TOP	2882- 862
LANS	3104-1084
KC	3156-1136
RTD	3220-1200

API NOT ASSIGNED
 OLD INFO: OPERATOR WAS TOM ALLAN, #1 KALTZ, SPD 7/22/
 42, SET 8 5/8 " 66, 5 1/2 " 3173, COMP. AS P 435 BOPD, LKC
 OH 3173-3220, CONTR: UNKNOWN
 NO DST'S
 MICT - CO, (LKC OH), AC 6500 G, SWB DWN & REC 12 BOPH,
 POP
 NEW INFO: 12/7/83, RE-ENTERED EST 12/10/83, WSH DWN,
 PROD CSG ALREADY IN HOLE, MICT - CO, PF (LKC) 3196-99 &
 3211-14, AC 250G (MA), SWB DWN, REC 18 BTF (33% OIL),
 POP, P 6 BOPD

COPYRIGHT 1984
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS