

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-20067-00-00
Spot: CSESWNW Sec/Twnshp/Rge: 13-3S-19W
2970 feet from S Section Line, 4290 feet from E Section Line
Lease/Unit Name: MILLER Well Number: 4
County: PHILLIPS Total Vertical Depth: 3390 feet

Operator License No.: 5242 Conductor Pipe: Size feet:
Operator Name: PETROLEUM MANAGEMENT, INC Surface Casing: Size 8.625 feet: 209 W/140 SXS.
Address: 14201 EAST CENTRAL 10/19 Production: Size 4.5 feet: 3389 W/225 SXS. 110.18
WICHITA, KS 67230 Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 10/19/2000 1:00 PM
Plug Co. License No.: 5242 Plug Co. Name: PETROLEUM MANAGEMENT, INC.
Proposal Rcvd. from: LARRY WALLERT Company: PETROLEUM MANAGEMENT, INC. Phone: (316) 733-5600

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 10% gel and hulls.

Plugging Proposal Received By: HUBERT DEINES Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 10/19/2000 2:00 PM KCC Agent: HUBERT DEINES

Actual Plugging Report:
8 5/8" to 209' w/140 sxs. 4 1/2" to 3389' w/225 sxs.
Tied onto annulus and pumped 30 sxs cement.
Max. P.S.I. 400#. S.I.P. 100#.
Tied onto 4 1/2" production casing and pumped 170 sxs cement with hulls.
Max. P.S.I. 600#. S.I.P. 200#.

RECEIVED
STATE CORPORATION COMMISSION
NOV 3 2000
11-3-2000
CONSERVATION DIVISION
Wichita, Kansas

Remarks: ALLIED CEMENTING COMPANY. THIS LEASE A/K/A EHM-STUTTGART #204.

Plugged through: CSG

District: 04 Signed [Signature] (TECHNICIAN)

INVOICED
DATE 11/6/00
INV. NO. 2001060937

OCT 31 2000

PETROLEUM MANAGEMENT, INC. #4 MILLER 13-3-19W
 WICHITA, KS. SE SW NW
 Contr. RED TIGER DRLG. CO. Cty. PHILLIPS
 Geol. BILL PETERSEN Pool STUITGART
 E. 2006 KB. Cm. 2/24/69 Cp. 6/12/69 IP CO IPP 40 BORD+
 50%W/LKC 3136-3286
 API 15-147-20,067

SMP	Tops	Depth	Datum	Csg.
				8-5/8" 209/140 EX; 4 1/2" 3385/225 EX
ANH		1497	+ 509	DST 3120-3140/60", WB 45", 8' DRLG M, BHP
B ANH		1526	+ 480	28-19#/90", FP 19-15#
TOP		2888	- .882	DST 3143-3164/60", SB, 240' GIP, 30' FO,
HEEB		3083	-1077	180' HOOM, 68' O&WOM, BHP 1050-1038#
TOR		3110	-1104	90", FP 28-145#
LANS		3128	-1122	DST 3213-3233/60", WB, 300' GIP, 90' FO,
BKC		3349	-1343	180' MO, BHP 1047-992#/90", FP 18-93#
TD		3390	-1384	DST 3237-3668/60", WB, 78' SOOM, BHP 1334-
				1334#/90", FP 28-53#
				DST 3262-3306/60", WB, 90' MO&OOM, BHP
				1343-1324#/90", FP 37-69#
				PF /3282-86, A 250, 2100' FIH, 450' OIL, SWB
				& REC 36 BBLs, TST 5 HRS 4 1/2 BPPH/50% OIL, FP
				3303-09, PF 3264-68, SET BP 3275, 1750' FIH
				350' OIL, SWB & TST 4 1/2 BPPH, 35% OIL, ACID
				250, PULLED PLUG, PF 3164-68; 3223-27, ACID
				500, RE-SET PKR 3164-68, A 250. (OVER)

INDEPENDENT OIL & GAS SERVICE
 WICHITA KANSAS

PETROLEUM MANAGEMENT, INC. #4 MILLER 13-3-19W
 SE SW NW

2200' FIH, 1100' OIL, SWB TST 1/2 HR DRY, A 200, PF 3202-04, 3209-22; 3189-98
 3136-40, A 250, 1200' FIH, SWB DRY, RE-AC 500, SWB DN, COMM TO 3203-04, A 1000
 T&R, POP